

## **Department of Property&Procurement**

## Government of the United States Virgin Islands



ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.774.9587 HTTP://DPP.VI.GOV

October 20, 2020

AMENDMENT #3- IFB061DPWT20 (C)— Qualified contractors to furnish all labor, tools, equipment, and supplies necessary for the Bolongo Bay Drainage-Phase I Project on St. Thomas, Virgin Islands

**DELETE: Old Bid Schedule Information** 

**INSERT:** New Bid Schedule Information

60201 (B) was added

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

BIDDERS **MUST** ACKNOWLEDGE RECEIPT OF THIS AMENDMENT WITH THEIR BID PROPOSAL.





## GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES DEPARTMENT OF PUBLIC WORKS DIVISION OF ENGINEERING

## BOLONGO BAY DRAINAGE IMPROVEMENT BID SCHEDULE - ADDENDUM NO. 3 - OCTOBER 2020 -

The undersigned contractor proposes to furnish all labor, equipment, machinery, material and contingencies for the completion of the Bolongo Bay Drainage Project as outlined on the Construction Drawings and Scope of Work. All works shall meet the conditions and regulations of the FP 14 Codes.

<u>No.</u>	DESCRIPTION	<u>UNITS</u>	QTY.	<u>PRICE</u>	TOTAL
15101	Mobilization	L.S.	1		
15201	Construction Survey and Staking	L.S.	1		
15401	Material Testing	L.S.	1		
1 <i>57</i> 01	Erosion Control - Silt Fence	L.F.	100		
40101(A)	Asphalt Concrete Pavement (Class A, Grade D) Type 1 Smooth in Place 4" (135 S.F.)	Ton	3.5		
60104(A)	Bioretention Basin, No.1 w/ Forebay - In Place	S.F.	25,000		
60104(B)	Bioretention Basin, No.2 - In Place	S.F.	3,500		
60201(A)	Trench Drain w/ Cast Iron Grates - In Place - (43 C.Y.) (86 L.F.)	EA.	1		
60201(B)	Catch Basin - A - with Removable Grate - In Place - (3 C.Y.)	EA.	2		
60201(C)	Box Culvert w/ Access Cover - In Place - (6.5 C.Y.)	EA.	2		
60201(D)	Oil/ Solid Separator - In Place	EA.	1		
60201(E)	15" Dia. Reinforced Concrete Pipe, CL III - In Place (13 EA.)	L.F.	104		
60201(F)	24" Dia. Reinforced Concrete Pipe, CL III - In Place (17 EA.)	L.F.	133		
60201(G)	15" HDPE Culvert - In Place	L.F.	202		
60201(H)	24" HDPE Culvert - In Place	L.F.	183		
60201(I)	Sand cover over Pipe	C.Y.	100		
60801(A)	Paved Water Way Type IV (3 Feet Wide, 645 L.F.)	S.Y.	215		
60801(B)	3' Wide & 5' Wide Paver Swales - In Place	EA.	1		
60801(C)	Turf Stone Beach Swale - In Place (210' x40')	S.Y.	934		
60801(D)	Bio Swale (Dry Creek Bed) - In Place (600'x10')	S.Y.	667		
60801(E)	Remove Tennis Court & Fencing & Install Techno-bloc Permeable Pavers	S.F.	6,000		
63501	Temporary Trench Box Protection & Water Remediation Equipment	L.S.	1		
	TOTAL				
	Prepared by Contractor:				