



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPR.VI.GOV](http://DPR.VI.GOV)



August 11, 2016

AMENDMENT #2 IFB011DPWT16 (C) Coki Point Road- Phase II (Route 388)

INSERT: ***Questions and Answers***

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED

BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT WITH THEIR BID PROPOSAL.

QUESTION & ANSWER(s):

1. Will the Surveyor be required to close the points that were discovered to be incorrect?
No. Just confirm and report to DPW Engineer of Record or Inspector.
2. Will Silt Fence be required for the entire length? The notes say it is identified on the plans, but I have been unable to locate it.
No. Only for the discharge area at Station 11+31.57 as indicated on plan.
3. Will we need a Turbidity curtain?
No. DPNR hasn't confirmed its need.
4. Most of the pipe culvert will be under the water table and there is no line item for dewatering.
Any water encountered during excavation and installation of storm drainage system should be brought to the attention of the EOR.
5. Where are the Gabion Baskets on the plan?
Station 0+50 Route 388. The gabion baskets are located adjacent to the Vinny's Food Mobile. Depending on the construction method implemented, they may not need to be disturbed.
6. Rigid pavement is under an Asphalt line item.
50101-0000 Rigid Pavement
7. Is Highway mesh to be used as reinforcement.
Yes. W5.5/w5.5" x 12" wire mesh or No. 2 bars spaced at 9" centers long and 12" centers transverse.
8. Is 3800 psi concrete to be used for the rigid pavement.
No. 4000 PSI.
9. Detail #2 on C6 is for a trench, not pavement repair.
This detail may be utilized at 11+34.26 to crest of hill. This area wasn't probed with the GPR.
10. How are we to maintain 2-way traffic 24 hrs/day. Will a signal light be sufficient?
Dependent on your approved traffic control plan. If necessary, you may use signal light for after hours while flaggers aren't present.
11. The line item for plantings, is that strictly reseeding?
Yes. Drought resistant type, i.e. manila zosia etc.
12. Are all permits obtained for this project? The notes read as if the contractor will be responsible to the EPA and DPNR for permits.
As indicated during the site visit, DPW will be responsible for obtaining the permits.
13. The utility pole to be relocated, is the contractor to coordinate with WAPA to move it and is that to include service relocation as well. Some homes will not be able to use their existing service access.

I believe the utility pole belongs to Innovative. In the event it has to be relocated, the contractor will be responsible for coordination with the respective utility owner.

14. Is the aggregate base to be 12" throughout the project?

Six inches (6")

15. There is going to be a tipping fee at the landfill which is close to \$65/ton for waste. Is Public Works going to be able to get that waived.

As it is, those rates are not in effect as yet. In the event they are implemented, then we will work with the winning contractor and VIWMA to resolve any issue that may arise.