



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT THREE (3)

March 25, 2019

TO:

SUBJECT: IFB019DPWC19(C) Repairs to Estate Union and Mt. Washington and Sally's Fancy Roads, East End, St. Croix, V.I.

INSERT: New Bid Sheet: Road Number 2, changed units of measure from C.Y to S.Y

DELETE: Old Bid Due Sheet

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid



**GOVERNMENT OF
THE VIRGIN ISLANDS OF THE UNITED STATES**

PUBLIC WORKS DEPARTMENT
6002 Estate Anna's Hope
Christiansted, St. Croix, V.I. 00820-4428

Tel: (340) 773-1290
Fax: (340) 773-6865

DIVISION OF ENGINEERING

PROJECT:	Scope of Work for Road Repairs at Union & Mt. Washington and Sallys Fancy	Page 1 of 2
DATE:	Monday, March 25, 2019	
PREPARED BY:	Eran Flemming	Addendum #1



ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
Sallys Fancy - Roadway No.1					
RIGID PAVEMENT LENGTH = 1,900 L.F ROAD WIDTH = 15 L.F					
30301	Road Reconditioning (Grading)	19	Stations		
30101	Untreated Aggregate (1/4"-3/4" compacted crushed stone base 8" depth)	704	C.Y		
40101(A)	Structural concrete in place for roadway (1,900'x15'x8"thick). 3/8" rebars shall be utilized @10" O.C for slob	3167	S.Y		
Sallys Fancy - Roadway No.2					
RIGID PAVEMENT LENGTH = 430 L.F ROAD WIDTH = 20 L.F					
30301	Road Reconditioning (Grading)	4.3	Stations		
30101	Untreated Aggregate (1/4"-3/4" compacted crushed stone base 8" depth)	212	C.Y		
40101(A)	Structural concrete in place for roadway (425'x20'x8"thick). 3/8" rebars shall be utilized @10" O.C for slob	956	S.Y		
Union & Mt. Washington - Five Entrances to be Excavated and reconstructed with Concrete					
AREA OF ENTRANCE = 155 S.Y					
30301	Excavation of Roadways for the contruction of Low water Crossing	170	C.Y		

60801	Construction of five (5) Low Water Crossing to include all forming, rebars and granular fill. David Oliver Drive, Tamrind Drive, Corry Drive, Sun Set Drive & Blue Dolphin Drive.	775	S.Y		
Misc.	Materials Testing	1	LS		
15101	Mobilization	1	LS		

TOTAL =====>

Duration of Project - 120 calendar days

Total cost for the project _____

Licensed Contractor _____

President of Company _____

Note: The undersigned Contractor acknowledges that the quantities included on the Bid Sheet are estimated values. It is the Contractor's responsibility to ascertain that the required material and quantities are included in the Bid Sheet in the event that there is a discrepancy between what the Contractor estimates is required to complete said project. Any discrepancies in values or material required must be identified at the time of the Pre-Bid meeting. Once the contract is executed, the Contractor will be required to complete the project based on selected bidder's contractual agreement cost.