

BID SCHEDULE
GOVERNMENT OF THE VIRGIN ISLANDS
DIVISION OF PERSONNEL/ST. THOMAS
3438 Kronprindsen Gade GERS Building, 3rd Floor Ste

<u>No.</u>	<u>DESCRIPTION</u>	<u>UNITS</u>	<u>QTY.</u>	<u>NUMBERS</u> <u>UNIT PRICE</u>	<u>TOTAL (\$)</u>
1	MOBILIZATION	LS	1.00		
2	REMOVE AND DISCARD OF EXISTING CARPET	SF	5,684.00		
3	INSTALL NEW CERAMIC FLOOR TILES	SF	8,000.00		
4	REMOVE/REPLACE EXISTING DRY-WALL WITH 5/8" GYPSUM BOAR ONE SIDE OF STEEL STUDS INTERIOR WALL	SF	200.00		
5	REMOVE/REPLACE EXISTING DRY-WALL WITH 5/8" GYPSUM BOAR TWO SIDE OF STEEL STUDS INTERIOR WALL	SF	3,012.00		
6	SUPPLY/INSTALL DRYWALL WITH 5/8" GYPSUM BOAR TWO SIDE OF STEEL STUDS INTERIOR WALL	SF	500.00		
7	REMOVE/INSTALL 36"x80" INTERIOR GLASS DOORS INCLUDING HARDWARE	EA	3.00		
8	REMOVE/INSTALL INTERIOR GLASS WINDOWS INCLUDING WOOD TRIM	EA	2.00		
9	REMOVE/INSTALL NEW RECEPTION WINDOW AND RECEPTION COUNTER	LS	1.00		
	REMOVE/INSTALL EXTERIOR GLASS DOOR LOCATED CONFERENCE ROOM	EA	1.00		
10	INSTALL NEW 4" PAINTED WOOD BASE BOARD	LF	1,400.00		
11	PAINT INTERIOR WALLS USE ONE COAT OF OF PRIMER AND TWO COATS OF A DURABLE LATEX PAINT.	SF	3,712.00		
12	MOVING OF FURNISHINGS AND EQUIPMENTS	LS	1.00		
13	INSPECT CEILING TILE GRID AND REPLACE ANY DAMAGED SECTIONS WITH SAME. (2' - 0 x 2' - 0")	EA	150.00		
14	PERFORM INSPECTION ELECTRICAL COMPONENTS TO ENSURE INTEGRITY: ELECTRICAL PANELS, JUNCTION BOXES, LIGHT FIXTURES, CONDUITS, OUTLET BOXES.	LS	1.00		
TOTAL (NUMBERS)					\$ _____
TOTAL (WORDS) _____					
CONTRACTOR'S NAME: _____					
CONTRACTOR'S SIGNATURE: _____					DATE: _____
PREPARED BY: DPW - ENG. DIVISION					
DATE: 08/7/2019 (Revised Bid Schedule)					