



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.774.9587

HTTP://DPP.VI.GOV



October 8, 2020

AMENDMENT #1- IFB059DOET20 (C)- Playground and Basketball Court Renovation at the Ulla Muller Elementary School on St. Thomas, Virgin Islands

DELETE: Old Itemize Bid Sheet Information

INSERT: New Itemize Bid Sheet Information

Questions and Answers

1. Please specify a post diameter for the Bison Basketball hoop. Available sizes are 4" and 5".
 - a. **See revised Itemized bid sheet, item #2, and sample cut sheet.**
2. Please clarify if tires on site are to be disposed of?
 - a. **Existing playground tires shall remain on site.**
3. Item #1 on the bid sheets calls out "Court Finish Material", is this an error? Should item #4 include labor only?
 - a. **See revised Itemized bid sheet, Line item #1.**
4. Item #8 on the bid sheet has no quantity, please correct.
 - a. **Item #8 is a lump sum cost.**
5. At the time of this question, there are no fees for disposal at the Bovoni Landfill, this is expected to change prior to the start of the project. Please confirm if dump fees will be an acceptable change order in implemented during the project?
 - a. **It was confirmed that VIWMA intends to implement tipping fees. Include tipping fees in Line item #7**

6. Please define what is required for temporary fencing around the area of demolition.
 - a. **The contractor shall schedule demolition utilizing the least amount of time and selective site disturbance. Note: *No major earthwork is anticipated.***

7. There are several old post foundations located in the court surface. Please confirm if these can be left in place and covered over neatly or if they should be removed and infilled?
 - a. **The old post foundations shall be made flush with the court sub surface and filled as required.**

8. What signage is required as part of Item #1.
 - a. **Basic Construction safety signage is required around the work zone.**

9. Please confirm if the court surface is intended to be one or multiple colors?
 - a. **The finished court shall be one solid color with contrasting line court lines. All colors shall be submitted to and approved by VIDE.**

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT WITH THEIR BID PROPOSAL.



THE VIRGIN ISLANDS
DEPARTMENT OF EDUCATION



Office of the Commissioner

Main:
1834 Kongens Gade, Charlotte Amalie
St. Thomas, U.S. Virgin Islands 00802-6746
Tel: 340/ 774-0100 • Fax: 340/ 779-7153

St. Croix:
2133 Hospital Street, Christiansted
St. Croix, U.S. Virgin Islands 00820-4665
Tel: 340/ 773-1095 • Fax: 340/ 773-9579

ADDENDUM A

**Playground and Basketball Court Renovation
Uller Muller Elementary School
St. Thomas/ St. John School District**

ITEMIZED BID SHEET

Item No.	Item Description	Quant.	Unit Price	Total
1.0	Safety measures to include temporary fencing (no or chain link fencing) and safety signage.	1 LS	\$	\$
2.0	Remove and replace existing basketball rims, backboards and damaged poles with new Bison 5 9/16" gooseneck style pole or approved equal. Complete installation shall include poles backboards, rims and nets for each rim.	2 EA	\$	\$
3.0	Pressure wash the existing court.	4,386 SF	\$	\$
4.0	Resurface court with Sportmaster "Standard Court System" paint and required surface preparation products or approved equal in accordance with the manufacturer's specification. (sportmaster.net)	4,386 SF	\$	\$
5.0	Install basketball court lines in accordance with the manufacturer's specification and industry standards. Note: Court and line colors to be chosen by VIDE.	1 LS	\$	\$
6.0	Provide and install Bison, Inc. "Outdoor Safe Stuff Pole Padding" or approved equal.	2 EA	\$	\$
7.0	Remove and legally dispose of damaged playground equipment including concrete footings. Finish grade to match existing.	1 LS	\$	\$
8.0	Project clean-up and close-out.	1 LS	\$	\$
TOTAL LUMP SUM COST				\$

Contractor: _____

Address: _____

Signature: _____ Date: _____

NOTES:

1. CONTRACTOR'S BID SHALL BE DISQUALIFIED IF ITEMIZED BID SHEET IS NOT FULLY COMPLETED WITH MATERIAL & LABOR UNIT COSTS, UNLESS OTHERWISE NOTED, AND THE LINE ITEM TOTALS.
2. THE QUANTITIES NOTED ABOVE ARE NOT NECESSARILY EXACT, AND THE ITEMS NOTED DO NOT NECESSARILY MAKE UP ALL THE WORK REQUIRED FOR THE COMPLETE CONSTRUCTION AND PROPER OPERATION OF THE PROJECT. THE ITEMS NOTED, WILL BE USED IN ESTABLISHING IF THE COST, WHICH ARE BEING SUBMITTED BY THE BIDDER, ARE WITHIN THE CURRENT ACCEPTABLE PRICES BEING USED IN THE U.S. VIRGIN ISLANDS CONSTRUCTION MARKET. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTING A TOTAL LUMP SUM COST FOR THE COMPLETE PROJECT.
3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ESTABLISH EXACT QUANTITIES BASED ON DOCUMENTS ISSUED AND SITE VISITS CARRIED OUT, FOR A TOTAL LUMP SUM COST TO CONSTRUCT THE PROJECT.
4. ALL PRICES BEING SUBMITTED FOR WORK TO BE DONE SHALL INCLUDE THE CONTRACTOR'S OVERHEAD TAXES AND PROFIT ALONG WITH ALL COSTS FOR MATERIALS, EQUIPMENT AND MANPOWER NECESSARY TO FACILITATE PROPER, SAFE, AND TIMELY COMPLETION OF THE PROJECT.
5. UNIT PRICES SUBMITTED ON THE ITEMIZED BID SHEET SHALL BE UTILIZED FOR ANY CREDITS OR DEBITS TO THE PROJECT; WHICH, IF NECESSARY, SHALL BE ADDRESSED AS A CHANGE ORDER TO THE PROJECT.

END OF ITEMIZED BID DOCUMENT