



# Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.774.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



August 27, 2021

## **AMENDMENT ONE (1) IFB080DHSC21(C)—Construction of a Generator Room at Mars Hill Head Start, St. Croix, U.S. Virgin Islands**

**INSERT**

**Attached Revised Scope of Work**

**DELETE**

**Original Scope of Work**

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT WITH THEIR BID PROPOSAL.



# GOVERNMENT OF THE VIRGIN ISLANDS OF THE UNITED STATES

PUBLIC WORKS DEPARTMENT  
6002 Estate Anna's Hope  
Christiansted, St. Croix, V.I. 00820-4428

Tel: (340) 773-1290  
Fax: (340)773-6865

## DIVISION OF ENGINEERING

PROJECT:	Construction of a Generator Room at Mars Hill Head Start, located at F'sted	PAGE 1 OF 1  Revised
DATE:	Wednesday, August 25, 2021	
PREPARED BY:	Eran Flemming	

Generator Room Dimension					
Length = 20L.F		Width = 8 L.F		Height = 9 L.F	
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
Generator Room					
1	Site work fine grading for slab with machine	1	L.S		
2	Granular fill for foundation (quarry tailing)	12	C.Y		
3	Structural concrete for spread footing, including forms, reinforcing steel	5	C.Y		
4	Structural concrete slab in place with 6x6 - W1.4xW1.4 mesh, troweled and screed finish, 3000 psi for the Generator room and concrete pad.	4	C.Y		
5	Structural concrete in place, for columns, includes forms, reinforcing steel	4	C.Y		
6	Structural concrete, in place, bond beam, includes forms reinforcing steel and finishing.	3	C.Y		
7	Concrete block 8"x8"x16" hallow, normal weight, 2000psi	570	S.F		

8	Structural concrete, in place, for the roof, to include all forms, reinforcing steel and finishing	5	C.Y		
9	Concrete finishing (plastering/stucco) of walls	1116	S.F		
10	Paints & coating, walls & ceiling primer and 2 coats, smooth finish	1332	S.F		
11	Concrete block, decorative 8"x16"x6" thick, hallow	50	S.F		
12	Installation of heavy guage aluminum louver window2 (3'x4')	2	each		
13	Hallow core, 1-3/4" thick, full panel, 20 Ga., double door, including frame and dead bolt, bronze lockset for a 6'x7' opening.	1	each		
14	Removal of picket fence (6'Hx8'wide)	48	S.F		
15	Removal and replacement of fuel tak to include the gas lines reconnection	1	L.S		
16	Extension (4'x6'-3")of the concrete pad that supports the fuel tank	25	s.f		

Total Cost

Licensed Contrator \_\_\_\_\_

Contractor Signature \_\_\_\_\_ Date \_\_\_\_\_

Project Duration - sixty calendar days

*Paul Fleming*  
 PUBLIC WORKS DEPARTMENT  
 ST. CROIX  
 VIRGIN ISLANDS