



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.774.9587

HTTP://DPP.VI.GOV



July 28, 2021

AMENDMENT THREE (3) IFB060SPRC21(C)— Cramer's Park Pavilions Hurricane Repair Project, St. Croix, U.S. Virgin Islands

INSERT QUESTIONS AND ANSWERS

Q1 During walk-through, it was noticed that the existing pavilions were fed from electrical panel in the substation electrical building. Please confirm that the new pavilions will be fed the same way. If yes, is a new feeder, riser, and panel required at the substation? If not, will new meters, weather heads, and risers be required at each new pavilion location?

A1 The five (5) new pavilions will be fed from the existing Electrical Substation Building. The existing weather head, meter, and panel in the existing Electrical Substation will be replaced with new equipment. The pavilions will be supplied with power via ¾" conduit with 6 Gauge wire inside it running 3' underground. Each of the new pavilions will have a Lockable Electrical Panel with dimming switch inside the panel; see Sheet E1: FLOOR PLAN ELECTRICAL, Detail 1 FLOOR PLAN—ELECTRICAL for typical electrical layout at all pavilions.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT WITH THEIR BID PROPOSAL.