

**GOVERNMENT OF  
THE VIRGIN ISLANDS OF THE UNITED STATES  
DEPARTMENT OF PUBLIC WORKS**

Division of Engineering  
Department of Agriculture  
Bordeaux Cistern - Parcel No. 115-9 - BID SCHEDULE

<u>No.</u>	<u>DESCRIPTION</u>	<u>UNITS</u>	<u>QTY.</u>	<u>PRICE</u>	<u>TOTAL</u>
1	Mobilization	L.S.	1		
2	Contractor Testing	L.S.	1		
3	Silt Fence Erosion Control	L.F.	110		
4	Excavation	C.Y.	175		
5	Crushed Stone Base Installation	C.Y.	27		
6	Polyethylene Vapor Barrier	S.F.	2,200		
7	Reinforced Concrete Footings, Slab, Walls & Roof	C.Y.	200		
8	Metal Gutting w/ 2x8 Gutter Attachment	L.F.	82		
9	Install All Plumbing Lines, Leads, Pipes, Sleeves and Valves	L.S.	1		
10	Install Pump, Pressure Tank & Water Heater	L.S.	1		
11	Install Electrical Service, Outlets, Switches and Light Fixture	L.S.	1		
12	Splash Blocks	Ea.	5		
13	Cistern Hatch Covers	Ea.	5		
14	Elastomeric Roof Coating - Roof Slab	S.F.	1,981		
15	Concrete Waterproofing - Cistern Interior	S.F.	7,540		
16	Portland Cement Plaster Finish	S.F.	2,376		
17	Exterior Acrylic Latex Painting - Exterior Walls	S.F.	2,376		
18	3'0" x 6'-8" Metal Framed Vented Pump Room Door	Ea.	1		
	<b>GRAND TOTAL</b>				
	Prepared by:		Date		