



Government of the U.S. Virgin Islands  
**DEPARTMENT OF PUBLIC WORKS**

**PROJECT NAME: Estates Misgunst and Lerkelund  
 Road Repairs  
 St. Thomas, USVI (Routes 37 & 40)  
 BID SCHEDULE**

Item No.	Description	Quantity	Units	Unit Price	Total
<b>Road Length = 2795 ft    Road Width = 22 ft</b>					
15101-0000	Mobilization	1	LS		
15201-0000	Construction Survey & Staking	1	LS		
15401-0000	Contractor Testing	1	LS		
20102-0000	Clearing and Grubbing	1	LS		
40301-0400	Hot Asphalt Concrete Pavement, (Class A, Grade 1/2"), 2.5"	1140	TON		
41201-0000	Tack Coat	450	GAL		
41301-0600	Asphalt Pavement Milling, 2.5"	7771	SY		
63303-0500	Project Sign, 4 x 8 Plywood	2	EA		
63401-1500	Pavement Markings, Type H, 4" Solid (Double Yellow )	4206	LF		
63401-1500C	Pavement Markings, Type H, 12" Solid White Crosswalks	24	LF		
63401-1500E	Pavement Markings, Type H, 24" Solid White Stop Bars	48	LF		
63402-1500	Pavement Markings, Type H, 4" Solid (Double White)	5644	LF		
63406-0000	Raised Pavement Marker	141	EACH		
63501-0000	Temporary Traffic Control	1	LS		
<b>DRAKE'S SEAT PARKING LOT AREA: (172'L x 32'W)</b>					
40301-0400	Hot Asphalt Concrete Pavement, (Class A, Grade 1/2"), 2.5"	95	TON		
41201-0000	Tack Coat	35	GAL		
41301-0600	Asphalt Pavement Milling, 2.5"	612	SY		
63401-1500	Pavement Markings, Type H, 4" Solid (Yellow )	100	LF		
63402-1500	Pavement Markings, Type H, 4" Solid (White)	234	LF		