

[illegible]

<b>INTERIOR WORK</b>					
<b>Item No.</b>	<b>Description of Work</b>	<b>Qty.</b>	<b>Units</b>	<b>Unit Price</b>	<b>Total Cost</b>
15	Paint interior wall w/prime and 2 coats (Ensure all cracks and holes are treated with epoxy prior to priming)	1,779	SF		
16	Install 2 addition rafters between existing rafters (2"x10") equally spaced) to bring building into compliance with VI Code.	64	EA		
17	Use Simpson tiedown (Corner tiedown)	4	EA		
18	Use Simpson tiedown (Intermediate Rafters ) Straight	32	EA		
19	Use Simpson tiedown (Intermediate Rafters ) Angled	32	EA		
20	Remove/replace existing lighting (16 middle lighting and 9 side lighting)	16	EA		
21	Remove/replace sconce side lighting	9	EA		
22	Install slip resistant ceramic flooring	2400	SF		
23	Remove/replace sliding aluminum doors 72"x80"	2	EA		
24	Remove/replace wall divider 8'x30'	1	EA		
25	Continuity test and repair for electrical lighting connections	1	LS		
26	Remove existing middle lighting and replace w/ceiling fans	5	EA		
27	Install additional ceiling fans in north half of building	2	EA		
28	Remove/replace curtain rod hardware	8	EA		
29	Remove/replace screens	8	EA		
30	Remove/replace wood box over doorway	2	EA		
31	Remove/replace security cameras	3	EA		
32	Remove existing air conditioner	1	EA		
33	Rustproof and paint structural support rods	9	EA		
34	Rewire fire alarm and test	1	LS		
35	Install 2 additional ceiling fans on northern half of building	2	EA		
				<i>Subtotal</i>	
				<b>TOTAL</b>	