



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT THREE (3)

September 25, 2015

TO:

SUBJECT: IFB012DPWC15(C) Road Repairs to Queen Street and Fisher Street in Frederiksted, St. Croix.

DELETE: Old Bid Sheet Dated August 20, 2015

INSERT: New Bid Sheet Dated September 22, 2015

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.



GOVERNMENT OF
THE VIRGIN ISLANDS OF THE UNITED STATES

PUBLIC WORKS DEPARTMENT
6002 Estate Anna's Hope
Christiansted, St. Croix, V.I. 00820-4428

DIVISION OF ENGINEERING

Tel: (340) 773-1290
Fax: (340) 773-6865

PROJECT:
DATE: Addendum 09/22/2015
PREPARED BY:

PAGE 1 OF 1

Section 1 Fisher St 1534' from Fish Market to Oval Street Width varies 20'-40'					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
15101	Mobilization(7%)	1	L.S		
41301	Roadway Milling 2" depth Material to be transported to DPW stock	5189.00	S.Y		
41201	Tack Coat Grade RS-1	623.00	GAL		
40101(A)	2" Asphalt Concrete Pavement, CL-"A" GR,-"D" Type 1 Smoothness In Place	581	Tons		
63401(A)	Thermoplastic pavement marking 4"yellow center line	3,068	L.F		
Section 2 Queen St 2260' x 27' from Fisher St to Lagoon St					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
15101	Mobilization(7%)	1	L.S		
41301	Roadway Milling 2" depth Material to be transported to DPW stock	6780	S.Y		
41201	Tack Coat Grade RS-1	814	GAL		
40101(A)	2" Asphalt Concrete Pavement, CL-"A" GR,-"D" Type 1 Smoothness In Place	759	Tons		
63401(A)	Thermoplastic pavement marking 4" yellow center line	4520	L.F		

TOTAL COST

DURATION

120

The undersigned Contractor acknowledges that the quantities included on the Bid Sheet are estimated values. It is the Contractor's responsibility to ascertain that the required material and quantities are included in the Bid Sheet in the event that there is a discrepancy between what the Contractor estimates is required to complete said project. Any discrepancies in values or material required must be identified at the time of the Pre- Bid meeting. Once the contract is executed, the Contractor will be required to complete the project based on selected bidder's contractual agreement cost."

PUBLIC WORKS DEPARTMENT
ST. CROIX
VIRGIN ISLANDS
A/ST 9/22/2015

Licensed Contractor _____

Contractor Signature _____ Date _____