

ROUTE 388 (COKI POINT ROAD) BID SCHEDULE					
ITEM NO.	DESCRIPTION	UNIT	TOTAL	UNIT COST IN WORDS	TOTAL COST
15101-0000	MOBILIZATION	LUMP	1		
15201-0000	CONSTRUCTION SURVEY AND STAKING	LUMP	1		
15401-0000	CONTRACTOR TESTING	LUMP	1		
15701-0100	EROSION CONTROL	LUMP	1		
15801-0000	WATERING FOR DUST CONTROL (1000 Gallons per Mgal)	MGAL	20		
20103-0000	CLEARING AND GRUBBING	SQ. YD.	1,000		
20301-2400	REMOVAL OF SIGN	EACH	6		
20304-1000	REMOVAL OF STRUCTURES AND OBSTRUCTION	LUMP	1		
20315-0000	SAW CUTTING	L.F.	96		
20401-0000	ROADWAY EXCAVATION	CU. YD.	1,006		
25301-0000	GABION BASKETS	CU. YD	9		
30102-2100	AGGREGATE BASE, GRADING D	CU. YD.	503		
40301-0300	RIGID PAVEMENT	S.Y.	4,000		
40301-0500	HOT ASPHALTIC PAVING; CLASS B, GRADE D	TON	100		
41202-0000	TACK COAT	GAL	50		
60201-0700	18" PIPE CULVERT	L.F.	373		
60401-1000	MANHOLE, TYPE 1	EACH	2		
60404-1000	CATCH BASIN, NO. 3	EACH	5		
60902-1000	PORTLAND CEMENT CONCRETE CURB AND GUTTER, 13" DEPTH	L.F.	1,132		
61501-0100	SIDEWALK, CONCRETE 4"	S.Y.	452		
61502-1000	ACCESSIBILITY RAMP, CONCRETE	EACH	4		
61710-1100	GUARDRAIL SYSTEM G4, TYPE IV, CLASS B STEEL POST, FLARED	L.F.	180		
62632-0000	PLANTINGS	LUMP	1		
63304-0900	SIGNS, ALUMINUM PANELS, TYPE 3 SHEETING	EACH	5		
63401-1500	PAVEMENT MARKINGS, 634.08, TYPE H, 18" SOLID WHITE	L.F.	164		
63401-1700	PAVEMENT MARKINGS, TYPE H, 4" SOLID YELLOW	L.F.	3,154		
63501-0000	TEMPORARY TRAFFIC CONTROL	LUMP	1		
63641-0700	RELOCATE UTILITY POLE	EACH	1		
				GRAND TOTAL	