



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT TWO (2)

June 1, 2017

TO:

**SUBJECT: IFB012DPWC17(C) Route 75 Clifton Hill
Roadway Widening and Improvements, St. Croix**

INSERT: Questions & Answers

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.

Pre-Bid Questions

Project Name: Clifton Hill Road (Route 75)

Project Number: VI-0075(004)

<i>Contractor Request for Clarifications</i>	<i>Responses by DPW and Consultant</i>
1. In accordance with section 109.01 – Measure of Work, in the project supplemental specifications please provide the soil analysis data for our review. i.e. bores sample, soil identification and/or gradation. Soil data will be required in order to confirm the site conditions.	There is no soil analysis data available for this project.
2. Is rock blasting going to be acceptable for removal of solid rock on project if discovered?	Due to the close proximity of the residential development, no rock blasting will be permitted on the project.
3. Please confirm that line item 301 – Aggregate Base will be measured by the ton in the truck.	Item 301 will be measured by the ton in the hauling vehicle. (Based on ticketed loads) in accordance with 109.03 of FP-03
4. Plan sheets B1-B3 show the paving of 1 inch. Please confirm that this will be paid for under line item 40201-14.	This item will be paid under item 403 as revised.
5. Based on site visit there appears to be approximately 6 light poles that will require relocation. Please confirm what line item will this be paid under.	Adjustment of light poles and overhead lines will be under the utility agreement with WAPA/Viya.
6. Are the conduit and wiring on the bid schedule for the relocating of the light poles or new traffic signal system?	Conduit and wiring are for the relocated new traffic signals.
7. There is only 100 lf of wire and 1,522 lf of conduit show on the bid schedule. We would assume these numbers should be similar. Please confirm that these quantities are correct.	Quantities are correct. Electric service wire (100 lf) is for electric power only. For supply from source to signal controller the conduit runs (1,522 lf) is for the entire signal system pull box to pull box, connecting signal poles in the corners and connecting to the signal controller box.
8. How will line item 20441-0000, Waste – Cubic Yard, be measured in the field for payment.	According with subsection 204.16(e), measure waste by the cubic yard in its final position. Take initial cross sections of the ground surface after stripping over burden. Upon completion of the waste placement, retake cross sections before replacing overburden. According with subsection 203.05 (a), for disposal of material off the project limits, Contractor shall submit a signed copy of the disposal agreement before disposal begins.

9. Based on comments made during pre-bid about the neighborhood adjacent to the project and in accordance with FP-03 section 158.03 a., can line item 158.01 – Watering for Dust Control, be added to the bid sheet?	Specification Items 204 and 301 calls for the use of water to adjust the moisture content of the embankment material. If there is need for additional moisture, the project engineer will make that determination.
10. What class will the RCP be rated for?	Use Class II, but Contractor is recommended to confirm the class of RCP following table included in Eastern Federal Lands Highway standard detail E602-07. See attached copy.
11. Is there a staging area designated for line item 624.07's conserved topsoil?	The contractor along with DPW to determine a staging area between the existing roadway and the realigned roadway.
12. Please provide scope of work description and specifications for line item 646-32, Roadside Development.	Roadside Development corresponds to any landscaping or aesthetic treatment work to be performed in those areas where turf reinforcement mat will be installed. Contractor should provide provisions for plant establishment periods of a duration sufficient for expected survival in the highway environment. A minimum of a 1-year plant establishment is recommended.
13. Please confirm that bid item 615.01-01 – Sidewalk, Concrete – Square Yard, is duplicated on page D-3 and D-4.	Sidewalks to be constructed as shown on the plans.
14. Please provide a detail drawing of line item 61801-00 Concrete Barrier.	A detail of the typical concrete barrier cross section is being provided. The contractor to provide details of reinforcement to be approved by DPW.

