



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT ONE (1)

August 8, 2017

TO:

SUBJECT: IFB023DPWC17 (C) Road Repairs at Estate La Grande Princess, Christiansted, St. Croix.

INSERT: New Revised Bid Sheet Date Tuesday, August 8, 2017

DELETE: Old Bid Sheet Date Thursday July 13, 2017

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.



**GOVERNMENT OF
THE VIRGIN ISLANDS OF THE UNITED STATES**

PUBLIC WORKS DEPARTMENT
6002 Estate Anna's Hope
Christiansted, St. Croix, V.I. 00820-4428

Tel: (340) 773-1290
Fax: (340)773-6865

DIVISION OF ENGINEERING

PROJECT: Road Repairs at Estate La Grande Princesse	PG. NO.1
DATE: Tuesday, August 8, 2017	
PREPARED BY: Eran Flemming	

Revised

Road Repairs at Estate La Grande Princesse					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
ROAD SECTION 1 - ROAD LENGTH = 3,540'		ROAD WIDTH = 22'			
41301	Milling of Roadway	8653	S.Y		
41202	Tack Coat, Grade RS1	1038	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 1	969	Tons		
ROAD SECTION 2 (- ROAD LENGTH = 1,870'		ROAD WIDTH = 20'			
30301	Road Reconditioning	5.9	STA.		
30101	Granular Fill (1/4"-3/4" compacted crushed stone base 4" depth)	462	C.Y		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 2	466	Tons		
ROAD SECTION 3 - ROAD LENGTH = 887'		ROAD WIDTH = 22'			
41301	Milling of Roadway	2144	S.Y		
41202	Tack Coat, Grade RS1	260	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 3	243	Tons		

SUB-TOTAL

PUBLIC WORKS DEPARTMENT
ST. CROIX
VIRGIN ISLANDS

PROJECT:	Road Repairs at Estate La Grande Princesse	PG. NO.2
DATE:	Tuesday, August 8, 2017	
PREPARED BY:	Eran Flemming	

Revised

Road Repairs at Estate La Grande Princesse					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
ROAD SECTION 4 - ROAD LENGTH = 1,420		ROAD WIDTH = 22			
41301	Milling of Roadway	2132	S.Y		
41202	Tack Coat, Grade RS1	256	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 4	239	Tons		
ROAD SECTION 5 - ROAD LENGTH = 440'		ROAD WIDTH = 20'			
30301	Road Reconditioning	4.4	STA.		
30101	Granular Fill (1/4"-3/4" compacted crushed stone base 4" depth)	109	C.Y		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 5	110	Tons		
SECTION 7 - ROAD LENGTH = 540'		ROAD WIDTH = 14'			
30301	Road Reconditioning	5.4	STA.		
30101	Granular Fill (1/4"-3/4" compacted crushed stone base 4" depth)	94	C.Y		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 7	94	Tons		

SUB-TOTAL

PROJECT: Road Repairs at Estate La Grande Princesse	PG. NO.3
DATE: Tuesday, August 8, 2017	
PREPARED BY: Eran Flemming	

Revised

Road Repairs at Estate La Grande Princesse					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
ROAD SECTION 9 - ROAD LENGTH = 2,240'		ROAD WIDTH = 21'			
41301	Milling of Roadway	5226.7	S.Y		
41202	Tack Coat, Grade RS1	627	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 9	586	Tons		
ROAD SECTION 10 - ROAD LENGTH = 1,450'		ROAD WIDTH = 20'			
41202	Tack Coat, Grade RS1	387	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 10	361	Tons		
ROAD SECTION 11 - ROAD LENGTH = 660'		ROAD WIDTH = 20'			
30301	Road Reconditioning	6.6	STA.		
41202	Tack Coat, Grade RS1	163	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - 11	164	Tons		

SUB-TOTAL

PROJECT:	Road Repairs at Estate La Grande Princesse	PG. NO.4
DATE:	Tuesday, August 8, 2017	
PREPARED BY:	Eran Flemming	

Revised

Road Repairs at Estate La Grande Princesse					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
ROAD SECTION 13 - ROAD LENGTH = 3,420'		ROAD WIDTH = 20'			
30301	Road Reconditioning	34.20	STA.		
41202	Tack Coat, Grade RS1	912	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - I3	851	Tons		
ROAD SECTION 14 - ROAD LENGTH = 500'		ROAD WIDTH = 20'			
30301	Road Reconditioning	5.00	STA.		
30101	Granular Fill (1/4"-3/4" compacted crushed stone base 4" depth)	124	C.Y		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - I4	125	Tons		
ROAD SECTION 15 - ROAD LENGTH = 620'		ROAD WIDTH = 20'			
41301	Milling of Roadway	1378	S.Y		
41202	Tack Coat, Grade RS1	165	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - I5	154	Tons		
ROAD SECTION 16 - ROAD LENGTH = 1,070'		ROAD WIDTH = 18'			
41301	Milling of Roadway	2140	S.Y		
41202	Tack Coat, Grade RS1	257	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness for area - I6	240	Tons		

SUB-TOTAL

PROJECT:	Road Repairs at Estate La Grande Princesse	PG. NO.5
DATE:	Tuesday, August 8, 2017	
PREPARED BY:	Eran Flemming	

Revised

41202	Temporary Traffic Control (Minor)	1	Lump Sum		
15101	Mobilization	1	Lump Sum		

TOTAL

Licensed Contractor _____

Contractor's Signature _____ Date _____

Note: The undersigned Contractor acknowledges that the quantities included on the Bid Sheet are estimated values. It is the Contractor's responsibility to ascertain that the required material and quantities are included in the Bid Sheet in the event that there is a discrepancy between what the Contractor estimates is required to complete said project. Any discrepancies in values or material required must be identified at the time of the Pre-Bid meeting. Once the contract is executed, the Contractor will be required to complete the project based on selected bidder's contractual agreement cost.

Note: All milling materials (recycled Asphalt) shall be transported to DPW Compound