



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT FOUR (4)

April 20, 2018

TO:

SUBJECT: RFP-013-2018 (C) Repairs to Five Educational Campuses in the St. Croix School District, St. Croix.

INSERT: New Itemized List Dated April 19, 2018

DELETE: Old Itemized List

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.

Itemized List - John Woodson Junior High School
Updated April 19, 2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
1	Fire equipment cabinets, portable extinguisher, single, steel box, recessed, D.S. glass in door, aluminum door & frame, 8" x 12" x 27", excludes equipment	10441 353 1000	3	Ea.		
2	Fire extinguishers, dry chemical, pressurized, ABC all purpose type, portable, 9-1/2 lb	10441 613 2080	3	Ea.		
3	Scaffolding, steel tubular, regular, frame, buy, 5' high x 5' wide	01542 370 1150	50	Ea.		
4	Scaffolding, steel tubular, regular, accessory, cross brace, buy	01542 370 1500	50	Ea.		
5	Scaffolding, steel tubular, regular, accessory, guardrail post, buy	01542 370 1550	50	Ea.		
6	Scaffolding, steel tubular, regular, accessory, screw jack & plate, buy	01542 370 1650	100	Ea.		
7	Scaffolding, steel tubular, regular, accessory, plank, buy, 2" x 10" x 16' long	01542 370 1800	25	Ea.		
8	Selective demolition, chain link fences & gates, fence, posts, steel in concrete	02411 362 1000	2	Ea.		
9	Selective demolition, chain link fences & gates, fence, fabric & accessories, fabric, to 8' high	02411 362 1100	1125	L.F.		
10	Selective demolition, rubbish handling, dumpster, 40 C.Y., 10 ton capacity, weekly rental, includes one dump per week, cost to be added to demolition cost	02411 919 0840	60	Dump		
11	Concrete crack repair, structural repair by epoxy injection (ACI RAP-1), suitable for horizontal, vertical and overhead repairs, up to 1/8" (0.125") wide x 6" deep, manual injection with 2-part epoxy cartridge, excludes prep	03013 071 1420	100	L.F.		
12	Unit masonry stabilization, structural fabric method, primer	04012 041 0310	2500	S.F.		
13	Unit masonry stabilization, structural fabric method, apply filling/leveling paste	04012 041 0320	2500	S.F.		
14	Cleaning masonry, new construction, medium construction dust, by chemical, brush and rinse, excludes scaffolding	04013 020 0220	97480	SF		
15	Cleaning masonry, light restoration, average soil, biological staining, by chemical, low pressure wash, brush and rinse, excludes scaffolding	04013 020 0270	2500	S.F.		
16	Selective demolition, thermal and moisture protection, downspouts, including hangers	07050 510 0120	60	L.F.		
17	Selective demolition, thermal and moisture protection, gutters, metal or wood, edge hung	07050 510 0420	260	L.F.		
18	Roof deck insulation, fiberboard high density, 1-1/2" thick, R3.8, fastening excluded	07221 610 0130	50	S.F.		
19	Steel roofing panels, on steel frame, flat profile, zinc aluminum alloy finish, 1-3/4" standing seams, 10" wide, 22 gauge	07411 320 0735	4000	S.F.		
20	Soffit, PVC, white, solid	07467 310 0300	40	S.F.		
21	APP modified bituminous membrane, smooth surface flashing, 170 mils, torched	07521 310 2300	50	S.F.		
22	Steel downspouts, galvanized, round, corrugated, 5" diameter, 26 gauge	07712 310 5100	60	L.F.		
23	Galvanized steel gutters, half round or box, stock, 5" wide, 26 gauge	07712 330 2700	260	L.F.		
24	Door demolition, exterior door, single, 3' x 7' high, 1-3/4" thick, remove	08050 510 0200	10	Ea.		
25	Door demolition, interior wood door, 1-3/4" x 3'-0" x 6' -8", remove	08050 510 1000	20	Ea.		
26	Window demolition, aluminum, to 25 S.F.	08050 520 0240	49	Ea.		
27	Doors, hollow metal, commercial, steel, flush, full panel, hollow core, 1-3/8" thick, 20 ga., 3'-0" x 6'-8"	08131 313 0060	10	Ea.		
28	Door, wood, architectural, flush, interior, hollow core, 7 ply, H.P. plastic laminate, 1-3/8", 3'-0" x 6'-8"	08141 609 1780	20	Ea.		

Itemized List - John Woodson Junior High School
Updated April 19, 2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
29	Windows, aluminum, commercial grade, stock units, awning type, standard glass, 3'-0" x 4'-0" opening, incl. frame and glazing	08511 320 3910	31	Ea.		
30	Ceiling demolition, suspended ceiling, mineral fiber, 2 x 2 or 2 x 4, remove	09050 510 1200	58434	S.F.		
31	Ceiling demolition, wood tongue and groove, 1" x 4", remove	09050 510 2000	1700	S.F.		
32	Flooring demolition, vinyl composition tile, 12" x 12"	09050 520 0900	13727	S.F.		
33	Gypsum wallboard, on ceilings, fire resistant, w/compound skim coat (level 5 finish), 1/2" thick	09291 030 1195	200	S.F.		
34	Gypsum wallboard, on walls, fire resistant, w/compound skim coat (level 5 finish), 5/8" thick	09291 030 2195	10000	S.F.		
35	Suspended acoustic ceiling tiles, mineral fiber tile, lay-in, fine texture, 2' x 2' or 2' x 4', 3/4" thick	09512 310 1125	58434	S.F.		
36	Acoustic ceiling grid, 2' x 2'	09532 330 0300	19455	S.F.		
37	Interior ceilings, wood slats on heavy duty 15/16" t-bar grid, 4"-6" wide	09542 610 1000	1700	S.F.		
38	Flooring, vinyl composition tile, marbleized, 12" x 12" x 1/8"	09651 919 7350	13727	S.F.		
39	Paints & coatings, walls, concrete masonry units (CMU), smooth surface, first coat, latex, roller	09911 390 0410	2500	S.F.		
40	Painting walls, complete, on drywall or plaster, primer and 2 finish coats, with roller, including surface preparation	09912 372 1670	10200	S.F.		
41	Exterior shutters, roll-up, manual operation, aluminum, 3' x 4', includes frame	10711 319 0020	18	Ea.		
42	Selective demolition, countertop	12050 510 1200	251	L.F.		
43	Selective demolition, wall cabinets, wood, to 84" high	12050 510 3130	251	L.F.		
44	Custom cabinets, rule of thumb: kitchen cabinets, excl. counters & appliances, minimum	12322 310 9560	251	L.F.		
45	Countertops, stock, plastic laminate, 24" wide, includes backsplash, maximum	12362 313 0100	251	L.F.		
46	Metal ductwork, fabricated rectangular, 500 to 1000 lb., aluminum alloy 3003-H14, incl fittings, joints, supports & allow for a flexible connections field sketches, excludes as-built drawings and insulation	23311 313 0120	2000	LB		
47	Fans, roof exhauster, centrifugal, aluminum housing, bird screen, back draft damper, direct drive, 1/4" S.P., 320 CFM, 12" galvanized curb, 11" sq. damper	23341 610 7100	1	Ea.		
48	Fans, ceiling fan, paddle blade air circulator, 6,500 CFM high, 4,000 CFM low, 52", includes 3 speed switch	23342 310 3040	93	Ea.		
49	Condensing unit, air cooled, compressor, 1.5 ton, includes standard controls	23621 310 0050	1	Ea.		
50	Condensing unit, air cooled, compressor, 5 Ton, includes standard controls	23621 310 0500	10	Ea.		
51	Self-contained single package A.C., air cooled, for free blow or duct, constant volume, 3 ton cooling, excludes remote condenser	23811 920 0200	1	Ea.		
52	Split ductless system, cooling only, single zone, wall mount, 3/4 ton cooling	23812 610 0120	14	Ea.		
53	Split ductless system, cooling only, single zone, wall mount, 2 ton cooling	23812 610 0150	30	Ea.		
54	Switch devices, residential, single pole, #12/2, EMT & wire, 20', 20 amp, incl box & cover plate	26059 010 2280	2	Ea.		
55	Generator set, gas/gasoline, 3 phase 4 wire, 277/480 V, 125 kW, includes battery, charger, & muffler	26321 316 0800	1	Ea.		
56	High pressure sodium fixture, interior, recessed, round, 70 W, incl lamps and mounting hardware	26511 340 0700	20	Ea.		
57	TV systems, antenna, pole, 10'	27413 310 5130	2	Ea.		
58	Closed circuit television system (CCTV), industrial quality, for additional camera stations, add	28231 310 2600	2	Ea.		
59	Chemical termite control, slab and walls, commercial, maximum	31311 613 0200	30000	SF Flr.		

Itemized List - John Woodson Junior High School				Updated April 19, 2018		
	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
60	Chain link fence gates and posts, motor operators for gates, up to 20' wide swing, excludes electric wiring & excavation	32311 110 7815	2	Ea.		
61	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2" posts @ 10' OC, 6' high, includes excavation, & concrete, excludes barbed wire	32311 320 0800	100	L.F.		
62	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2-1/2" posts @ 10' OC, 8' high, includes excavation, in concrete, excludes barbed wire	32311 320 0920	1025	L.F.		
TOTAL						

NOTES:

1) EVERY LINE ITEM DETAILED ABOVE ARE CONSIDERED ADD/DELETES AND THE OWNER RESERVES THE RIGHT TO REMOVE ANY TASK AS IS DEEM REQUIRED TO MEET THE GOVERNMENT'S OBJECTIVE UNDER THIS REQUEST FOR PROPOSAL.

2) PRICES BEING SUBMITTED FOR WORK TO BE DONE SHALL INCLUDE THE CONTRACTOR'S OVERHEAD TAXES AND PROFIT ALONG WITH ALL COSTS FOR MATERIALS, EQUIPMENT AND MANPOWER NECESSARY TO FACILITATE PROPER, SAFE, AND TIMELY COMPLETION OF THE PROJECT.

3) UNIT PRICES SUBMITTED ON THIS ITEMIZED BID SHEET SHALL BE UTILIZED FOR ANY CREDITS OR DEBITS TO THE PROJECT; WHICH, IF NECESSARY, SHALL BE ADDRESSED AS A CHANGE ORDER TO THE PROJECT.

Itemized List - Eulalie Rivera Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
1	Scaffolding, steel tubular, regular, frame, buy, 5' high x 5' wide	01542 370 1150	25	Ea.		
2	Selective demolition, gutting, building interior, commercial building, includes disposal, excludes dumpster fees, maximum	02411 921 1020	18000	S.F.		
3	Scaffolding, steel tubular, regular, accessory, cross brace, buy	01542 370 1500	25	Ea.		
4	Scaffolding, steel tubular, regular, accessory, guardrail post, buy	01542 370 1550	25	Ea.		
5	Scaffolding, steel tubular, regular, accessory, screw jack & plate, buy	01542 370 1650	50	Ea.		
6	Scaffolding, steel tubular, regular, accessory, plank, buy, 2" x 10" x 16' long	01542 370 1800	25	Ea.		
7	Selective demolition, chain link fences & gates, fence, posts, steel in concrete	02411 362 1000	120	Ea.		
8	Selective demolition, chain link fences & gates, fence, fabric & accessories, fabric, to 8' high	02411 362 1100	1145	L.F.		
9	Selective demolition, rubbish handling, dumpster, 40 C.Y., 10 ton capacity, weekly rental, includes one dump per week, cost to be added to demolition cost	02411 919 0840	70	Dump		
10	Asbestos remediation, plans and methods, building survey, commercial	02821 339 0100	1	Ea.		
11	Asbestos abatement equipment & supplies, buy, airless sprayer unit, 2 gun	02821 341 0300	1	Ea.		
12	Preparation of asbestos containment area, separation barrier, 2" x 4" @ 16", 1/2" plywood each side, 12' high	02821 342 0310	300	S.F.		
13	Preparation of asbestos containment area, cover surfaces with polyethylene sheeting, walls, each layer, 6 mil, incl. glue & tape	02821 342 0560	300	S.F.		
14	Bulk asbestos removal, remove VAT and mastic from floor by hand, includes disposable tools & 2 suits & 1 respirator filter/day/worker	02821 343 5000	42777	S.F.		
15	Mold remediation plans and methods, initial inspection, areas to 10000 S.F.	02871 316 0032	5	Total		
16	Mold remediation, mold abatement plan, areas to 10000 S.F.	02871 316 0095	5	Total		
17	Preparation of mold containment area, pre-cleaning, flat surfaces, HEPA vacuum & wet wipe	02871 316 6100	25000	S.F.		
18	Demolition in mold contaminated area, ceiling, gypsum board	02871 333 0250	42777	S.F.		
19	Concrete crack repair, structural repair by epoxy injection (ACI RAP-1), suitable for horizontal, vertical and overhead repairs, up to 1/8" (0.125") wide x 6" deep, manual injection with 2-part epoxy cartridge, excludes prep	03013 071 1420	740	L.F.		
20	Unit masonry stabilization, structural fabric method, primer	04012 041 0310	20	S.F.		
21	Unit masonry stabilization, structural fabric method, apply filling/leveling paste	04012 041 0320	20	S.F.		
22	Cleaning masonry, new construction, medium construction dust, by chemical, brush and rinse, excludes scaffolding	04013 020 0220	64005	SF		
23	Cleaning masonry, light restoration, average soil, biological staining, by chemical, low pressure wash, brush and rinse, excludes scaffolding	04013 020 0270	20	S.F.		
24	Floor grating, aluminum, heavy duty extruded plank, 1.8 lb./S.F., 3/4" D, field fabricated from panels	05531 310 1600	90	S.F.		
25	Selective demolition, wood framing, fascia boards, 2" x 8"	06050 510 3500	18	L.F.		

Itemized List - Eulalie Rivera Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
26	Selective demolition, wood framing, sheathing, 3/4", from roof	06050 510 6094	18600	S.F.		
27	Sheathing, plywood on roof, CDX, 3/4" thick	06163 610 0300	18600	S.F.		
28	Selective demolition, thermal and moisture protection, downspouts, including hangers	07050 510 0120	600	L.F.		
29	Selective demolition, thermal and moisture protection, gutters, metal or wood, edge hung	07050 510 0420	3250	L.F.		
30	Green roof systems, fluid applied rubber membrane, 215 mil thick, reinforced, not including insulation	07336 310 0560	1600	S.F.		
31	Steel roofing panels, on steel frame, flat profile, zinc aluminum alloy finish, 1-3/4" standing seams, 10" wide, 22 gauge	07411 320 0735	24688	S.F.		
32	Soffit, baked enamel on steel, 16 or 18 gauge	07467 310 0100	24	S.F.		
33	APP modified bituminous membrane, smooth surface flashing, 170 mils, torched	07521 310 2300	1600	S.F.		
34	Steel downspouts, galvanized, round, corrugated, 5" diameter, 26 gauge	07712 310 5100	600	L.F.		
35	Galvanized steel gutters, half round or box, stock, 5" wide, 26 gauge	07712 330 2700	3250	L.F.		
36	Gutter end caps, K type galvanized steel, 5"	07712 330 5080	50	Ea.		
37	Door demolition, exterior door, single, 3' x 7' high, 1-3/4" thick, remove	08050 510 0200	1	Ea.		
38	Door demolition, interior wood door, 1-3/4" x 3'-0" x 6'-8", remove	08050 510 1000	317	Ea.		
39	Doors, hollow metal, commercial, steel, flush, full panel, hollow core, 1-3/8" thick, 20 ga., 3'-0" x 6'-8"	08131 313 0060	2	Ea.		
40	Door, wood, architectural, flush, interior, hollow core, 7 ply, H.P. plastic laminate, 1-3/8", 3'-0" x 6'-8"	08141 609 1780	4	Ea.		
41	Window screens, wicket screen, inside window	08516 610 0500	200	S.F.		
42	Door hardware, school, single, exterior, incl. lever, panic device	08712 015 2250	2	Door		
43	Door hardware, school, single, interior, regular use, incl. lever handle	08712 015 2500	4	Door		
44	Ceiling demolition, suspended ceiling, mineral fiber, 2 x 2 or 2 x 4, remove	09050 510 1200	49578	S.F.		
45	Ceiling demolition, wood tongue and groove, 1" x 8", remove	09050 510 2040	4550	S.F.		
46	Walls and partitions demolition, gypsum wallboard, per s.f., nailed or screwed	09050 530 1000	9230	S.F.		
47	Gypsum wallboard, on walls, fire resistant, w/compound skim coat (level 5 finish), 5/8" thick	09291 030 2195	9230	S.F.		
48	Suspended acoustic ceiling tiles, mineral fiber tile, lay-in, fine texture, 2' x 2' or 2' x 4', 3/4" thick	09512 310 1125	49578	S.F.		
49	Acoustic ceiling grid, 2' x 2'	09532 330 0300	20170	S.F.		
50	Interior ceilings, wood slats on heavy duty 15/16" t-bar grid, 4"-6" wide	09542 610 1000	4550	S.F.		
51	Flooring, welding, vinyl seams, add	09651 610 8400	500	L.F.		
52	Flooring, vinyl composition tile, marbleized, 12" x 12" x 1/8"	09651 919 7350	42777	S.F.		
53	Paints & coatings, walls & ceilings, interior, concrete, drywall or plaster, latex paint, primer or sealer coat, smooth finish, brushwork	09912 372 0200	16600	SF		
54	Exterior shutters, roll-up, manual operation, aluminum, 3' x 4', includes frame	10711 319 0020	17	Ea.		

Itemized List - Eulalie Rivera Elementary School				Updated 4/19/2018		
	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
55	Flagpoles, aluminum, tapered, ground set, 20' high, excludes base or foundation	10751 610 0100	1	Ea.		
56	School equipment, basketball backstops, wall mounted, fixed, 6' extended, maximum	11662 313 1100	1	Ea.		
57	Selective demolition, countertop	12050 510 1200	317	L.F.		
58	Selective demolition, wall cabinets, wood, to 84" high	12050 510 3130	317	L.F.		
59	Custom cabinets, rule of thumb: kitchen cabinets, excl. counters & appliances, minimum	12322 310 9560	317	L.F.		
60	Countertops, stock, plastic laminate, 24" wide, includes backsplash, maximum	12362 313 0100	317	L.F.		
61	Bleachers, outdoor, portable, 5 tiers, 42 seats, 15' long	13341 653 0020	40	Seat		
62	Metal ductwork, fabricated rectangular, 500 to 1000 lb., aluminum alloy 3003-H14, incl fittings, joints, supports & allow for a flexible connections field sketches, excludes as-built drawings and insulation	23311 313 0120	1500	LB		
63	Fans, roof exhauster, centrifugal, aluminum housing, bird screen, back draft damper, direct drive, 1/4" S.P., 320 CFM, 12" galvanized curb, 11" sq. damper	23341 610 7100	1	Ea.		
64	Fans, ceiling fan, paddle blade air circulator, 6,500 CFM high, 4,000 CFM low, 52", includes 3 speed switch	23342 310 3040	19	Ea.		
65	Self-contained single package A.C., air cooled, for free blow or duct, constant volume, 3 ton cooling, excludes remote condenser	23811 920 0200	8	Ea.		
66	Split ductless system, cooling only, single zone, wall mount, 2 ton cooling	23812 610 0150	12	Ea.		
67	Service & panel, residential, w/18 branch breakers, w/RGS conduit & wire, 200 amp, incl 24' SE-AL cable, service eye, meter socket	26059 010 1230	1	Ea.		
68	Incandescent fixture, interior, ceiling/wall, surface mounted, metal cylinder, 75 W, incl lamps, mounting hardware and connections	26511 350 4900	30	Ea.		
69	Detection system, fire alarm signal bell 10" red 20-24 V P	28462 150 4610	5	Ea.		
70	Detection system, break glass station, excluding wires & conduits	28462 150 7000	1	Ea.		
71	Chain link fence gates and posts, motor operators for gates, up to 20' wide swing, excludes electric wiring & excavation	32311 110 7815	2	Ea.		
72	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2 1/2" posts @ 10' OC, 8' high, includes excavation, in concrete, excludes backstop	32311 320 0920	645	L.F.		
73	Fence, chain link, line posts, 16 ga., steel, galv, 3" x 21 x 0.203 wall, set in concrete, includes post cap and excavation	32311 365 0430	120	Ea.		
74	Decorative metal fences and gates, tubular picket, steel, staggered picket, 6' sections, 2" posts, 5' high, includes excavation	32311 910 5800	500	L.F.		
					TOTAL	

NOTES:

1) EVERY LINE ITEM DETAILED ABOVE ARE CONSIDERED ADD/DELETES AND THE OWNER RESERVES THE RIGHT TO REMOVE ANY TASK AS IS DEEM REQUIRED TO MEET THE GOVERNMENT'S OBJECTIVE UNDER THIS REQUEST FOR PROPOSAL.

2) PRICES BEING SUBMITTED FOR WORK TO BE DONE SHALL INCLUDE THE CONTRACTOR'S OVERHEAD TAXES AND PROFIT ALONG WITH ALL COSTS FOR MATERIALS, EQUIPMENT AND MANPOWER NECESSARY TO FACILITATE PROPER, SAFE, AND TIMELY COMPLETION OF THE PROJECT.

3) UNIT PRICES SUBMITTED ON THIS ITEMIZED BID SHEET SHALL BE UTILIZED FOR ANY CREDITS OR DEBITS TO THE PROJECT; WHICH, IF NECESSARY, SHALL BE ADDRESSED AS A CHANGE ORDER TO THE PROJECT.

Itemized List - Alfredo Andrews Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
1	Scaffolding, steel tubular, regular, accessory, guardrail post, buy	01542 370 1550	25	Ea.		
2	Scaffolding, steel tubular, regular, accessory, screw jack & plate, buy	01542 370 1650	50	Ea.		
3	Scaffolding, steel tubular, regular, accessory, plank, buy, 2" x 10" x 16' long	01542 370 1800	25	Ea.		
4	Selective demolition, chain link fences & gates, fence, posts, steel in concrete	02411 362 1000	90	Ea.		
5	Selective demolition, chain link fences & gates, fence, fabric & accessories, fabric, to 8' high	02411 362 1100	910	L.F.		
6	Selective demolition, rubbish handling, dumpster, 40 C.Y., 10 ton capacity, weekly rental, includes one dump per week, cost to be added to demolition cost	02411 919 0840	25	Dump		
7	Concrete crack repair, structural repair by epoxy injection (ACI RAP-1), suitable for horizontal, vertical and overhead repairs, up to 1/8" (0.125") wide x 6" deep, manual injection with 2-part epoxy cartridge, excludes prep	03013 071 1420	33	L.F.		
8	Unit masonry stabilization, structural fabric method, primer	04012 041 0310	1560	S.F.		
9	Unit masonry stabilization, structural fabric method, apply filling/leveling paste	04012 041 0320	1560	S.F.		
10	Cleaning masonry, new construction, medium construction dust, by chemical, brush and rinse, excludes scaffolding	04013 020 0220	66671	SF		
11	Cleaning masonry, light restoration, average soil, biological staining, by chemical, low pressure wash, brush and rinse, excludes scaffolding	04013 020 0270	1560	S.F.		
12	Selective metals demolition, manufactured or fabricated specialty item, 21-40 lb, remove whole or cut up into smaller pieces, excl shoring, bracing, cutting, loading, hauling, dumping	05050 510 0350	20	Ea.		
13	Drilling holes in steel for anchors, up to 1/4" deep, 5/8" diameter, incl bit & layout, excludes anchor	05052 115 1950	20	Ea.		
14	Drilling holes in steel for anchors, 5/8" diameter, incl bit & layout, excludes anchor, for each additional 1/4" depth, add	05052 115 1955	32	Ea.		
15	Welding structural steel in field, cost per welder, 1/8" dia, type 6011, excl operating engineer	05052 190 0020	10	Hr.		
16	Welding structural steel in field, single pass, 0.3 lb/LF, 1/4" thick, continuous fillet, down welding, type 6011	05052 190 1500	150	L.F.		
17	High strength bolt, 1/2" dia x 1-1/2" L, A325 Type 1, incl washer & nut	05052 325 0100	20	Ea.		
18	Metal floor decking, steel, non-cellular, composite, galvanized, 1-1/2" D, 18 gauge	05311 350 5120	400	S.F.		
19	Selective demolition, thermal and moisture protection, downspouts, including hangers	07050 510 0120	60	L.F.		
20	Selective demolition, thermal and moisture protection, gutters, metal or wood, edge hung	07050 510 0420	260	L.F.		
21	Selective demolition, thermal and moisture protection, roof edge, drip edge	07050 510 2220	260	L.F.		
22	Steel roofing panels, on steel frame, flat profile, zinc aluminum alloy finish, 1-3/4" standing seams, 10" wide, 22 gauge	07411 320 0735	4120	S.F.		
23	APP modified bituminous membrane, smooth surface flashing, 170 mils, torched	07521 310 2300	100	S.F.		
24	Steel downspouts, galvanized, round, corrugated, 5" diameter, 26 gauge	07712 310 5100	60	L.F.		
25	Galvanized steel gutters, half round or box, stock, 5" wide, 26 gauge	07712 330 2700	260	L.F.		
26	Drip edge, galvanized, mill finish, 8" wide	07714 310 0500	260	L.F.		

Itemized List - Alfredo Andrews Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
27	Roof vents, mushroom shape, for built-up roofs, aluminum	07722 310 0020	50	Ea.		
28	Door demolition, interior wood door, 1-3/4" x 3'-0" x 6'-8", remove	08050 510 1000	3	Ea.		
29	Window demolition, aluminum, to 25 S.F.	08050 520 0240	11	Ea.		
30	Doors, hollow metal, commercial, steel, flush, full panel, hollow core, for vision lite, add	08131 313 0120	12	Ea.		
31	Door, wood, architectural, flush, interior, hollow core, 7 ply, H.P. plastic laminate, 1-3/8", 3'-0" x 6'-8"	08141 609 1780	3	Ea.		
32	Windows, aluminum, commercial grade, stock units, awning type, standard glass, 3'-0" x 4'-0" opening, incl. frame and glazing	08511 320 3910	8	Ea.		
33	Door hardware, school, single, interior, regular use, incl. lever handle	08712 015 2500	3	Door		
34	Ceiling demolition, suspended ceiling, mineral fiber, 2 x 2 or 2 x 4, remove	09050 510 1200	54005	S.F.		
35	Flooring demolition, vinyl composition tile, 12" x 12"	09050 520 0900	21605	S.F.		
36	Suspended acoustic ceiling tiles, mineral fiber tile, lay-in, fine texture, 2' x 2' or 2' x 4', 3/4" thick	09512 310 1125	54005	S.F.		
37	Acoustic ceiling grid, 2' x 2'	09532 330 0300	10500	S.F.		
38	Flooring, vinyl composition tile, marbleized, 12" x 12" x 1/8"	09651 919 7350	21605	S.F.		
39	Paints & coatings, walls, concrete masonry units (CMU), smooth surface, first coat, latex, roller	09911 390 0410	1560	S.F.		
40	Signs, exterior, custom, interior illuminated, on pedestal, 84" x 30" x 12", not including foundation	10141 910 8100	1	Ea.		
41	Fire equipment cabinets, portable extinguisher, single, steel box, recessed, D.S. glass in door, aluminum door & frame, 8" x 12" x 27", excludes equipment	10441 353 1000	3	Ea.		
42	Fire extinguishers, dry chemical, pressurized, ABC all purpose type, portable, 9-1/2 lb	10441 613 2080	3	Ea.		
43	Exterior shutters, roll-up, manual operation, aluminum, 3' x 4', includes frame	10711 319 0020	3	Ea.		
44	Metal ductwork, fabricated rectangular, 500 to 1000 lb., aluminum alloy 3003-H14, incl fittings, joints, supports & allow for a flexible connections field sketches, excludes as-built drawings and insulation	23311 313 0120	1000	LB		
45	Fans, roof exhaust, centrifugal, aluminum housing, bird screen, back draft damper, direct drive, 1/4" S.P., 320 CFM, 12" galvanized curb, 11" sq. damper	23341 610 7100	2	Ea.		
46	Split ductless system, cooling only, single zone, wall mount, 2 ton cooling	23812 610 0150	3	Ea.		
47	Generator set, diesel, 3 phase 4 wire, 277/480 V, 125 kW, incl battery, charger, muffler, & day tank, excl conduit, wiring, & concrete	26321 313 2400	1	Ea.		
48	TV systems, antenna, pole, 10'	27413 310 5130	2	Ea.		
49	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2" posts @ 10' OC, 6' high, includes excavation, & concrete, excludes barbed wire	32311 320 0800	50	L.F.		
50	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2-1/2" posts @ 10' OC, 8' high, includes excavation, in concrete, excludes barbed wire	32311 320 0920	860	L.F.		
51	Fence, chain link, line posts, 16 ga., steel, galv, 3" x 21 x 0.203 wall, set in concrete, includes post cap and excavation	32311 365 0430	90	Ea.		
TOTAL						

NOTES:

1) EVERY LINE ITEM DETAILED ABOVE ARE CONSIDERED ADD/DELETES AND THE OWNER RESERVES THE RIGHT TO REMOVE ANY TASK AS IS DEEM REQUIRED TO MEET THE GOVERNMENT'S OBJECTIVE UNDER THIS REQUEST FOR PROPOSAL.

Itemized List - Alfredo Andrews Elementary School**Updated 4/19/2018**

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
--	-------------	------------	-----	------	-----------	------------

2) PRICES BEING SUBMITTED FOR WORK TO BE DONE SHALL INCLUDE THE CONTRACTOR'S OVERHEAD TAXES AND PROFIT ALONG WITH ALL COSTS FOR MATERIALS, EQUIPMENT AND MANPOWER NECESSARY TO FACILITATE PROPER, SAFE, AND TIMELY COMPLETION OF THE PROJECT.

3) UNIT PRICES SUBMITTED ON THIS ITEMIZED BID SHEET SHALL BE UTILIZED FOR ANY CREDITS OR DEBITS TO THE PROJECT; WHICH, IF NECESSARY, SHALL BE ADDRESSED AS A CHANGE ORDER TO THE PROJECT.

Itemized List - Pearl Larsen Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
1	Scaffolding, steel tubular, regular, frame, buy, 5' high x 5' wide	01542 370 1150	25	Ea.		
2	Scaffolding, steel tubular, regular, accessory, cross brace, buy	01542 370 1500	25	Ea.		
3	Scaffolding, steel tubular, regular, accessory, guardrail post, buy	01542 370 1550	25	Ea.		
4	Scaffolding, steel tubular, regular, accessory, screw jack & plate, buy	01542 370 1650	50	Ea.		
5	Scaffolding, steel tubular, regular, accessory, plank, buy, 2" x 10" x 16' long	01542 370 1800	25	Ea.		
6	Selective demolition, chain link fences & gates, fence, posts, steel in concrete	02411 362 1000	5	Ea.		
7	Selective demolition, chain link fences & gates, fence, fabric & accessories, fabric, to 8' high	02411 362 1100	700	L.F.		
8	Selective demolition, rubbish handling, dumpster, 40 C.Y., 10 ton capacity, weekly rental, includes one dump per week, cost to be added to demolition cost	02411 919 0840	25	Dump		
9	Structural concrete, in place, handicap access ramp (4000 psi), w/ 6" curb, railing both sides, 5' wide, includes forms(4 uses), Grade 60 rebar, concrete (Portland cement Type I), placing and finishing	03305 340 4535	20	L.F.		
10	Unit masonry stabilization, structural fabric method, primer	04012 041 0310	10000	S.F.		
11	Unit masonry stabilization, structural fabric method, apply filling/leveling paste	04012 041 0320	10000	S.F.		
12	Cleaning masonry, new construction, medium construction dust, by chemical, brush and rinse, excludes scaffolding	04013 020 0220	80119	SF		
13	Cleaning masonry, light restoration, average soil, biological staining, by chemical, low pressure wash, brush and rinse, excludes scaffolding	04013 020 0270	10000	S.F.		
14	Concrete block partitions, lightweight blocks, hollow, 2000 psi, 8" x 8" x 16", tooled joints both sides, includes mortar and horizontal joint reinforcing every other course, excludes scaffolding and vertical reinforcing	04221 034 1650	200	S.F.		
15	Selective demolition, thermal and moisture protection, downspouts, including hangers	07050 510 0120	60	L.F.		
16	Selective demolition, thermal and moisture protection, gutters, metal or wood, edge hung	07050 510 0420	220	L.F.		
17	Blanket insulation for floors/ceilings, fiberglass, unfaced, 6-1/4" thick, R 19, incl. spring type wire fasteners	07211 610 3010	15965	S.F.		
18	APP modified bituminous membrane, smooth surface flashing, 170 mils, torched	07521 310 2300	100	S.F.		
19	Steel downspouts, galvanized, round, corrugated, 5" diameter, 26 gauge	07712 310 5100	60	L.F.		
20	Galvanized steel gutters, half round or box, stock, 5" wide, 26 gauge	07712 330 2700	220	L.F.		
21	Roof vents, mushroom shape, for built-up roofs, aluminum	07722 310 0020	12	Ea.		
22	Door demolition, exterior door, single, 3' x 7' high, 1-3/4" thick, remove	08050 510 0200	1	Ea.		
23	Door demolition, interior wood door, 1-3/4" x 3'-0" x 6'-8", remove	08050 510 1000	4	Ea.		
24	Window demolition, aluminum, to 25 S.F.	08050 520 0240	7	Ea.		
25	Doors, hollow metal, commercial, steel, flush, full panel, hollow core, 1-3/8" thick, 20 ga., 3'-0" x 6'-8"	08131 313 0060	1	Ea.		
26	Door, wood, architectural, flush, interior, hollow core, 7 ply, H.P. plastic laminate, 1-3/8", 3'-0" x 6'-8"	08141 609 1780	4	Ea.		
27	Windows, aluminum, commercial grade, stock units, awning type, standard glass, 3'-0" x 4'-0" opening, incl. frame and glazing	08511 320 3910	4	Ea.		
37	Door hardware, school, single, exterior, incl. lever, panic device	08712 015 2250	1	Door		

Itemized List - Pearl Larsen Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
38	Door hardware, school, single, interior, regular use, incl. lever handle	08712 015 2500	4	Door		
28	Ceiling demolition, suspended ceiling, mineral fiber, 2 x 2 or 2 x 4, remove	09050 510 1200	39627	S.F.		
29	Flooring demolition, vinyl composition tile, 12" x 12"	09050 520 0900	26990	S.F.		
30	Suspended acoustic ceiling tiles, mineral fiber tile, lay-in, fine texture, 2' x 2' or 2' x 4', 3/4" thick	09512 310 1125	39627	S.F.		
31	Acoustic ceiling grid, 2' x 2'	09532 330 0300	800	S.F.		
32	Resilient flooring, rubber, sheet goods, 3' w, 1/4" thick	09651 610 6000	6000	S.F.		
33	Flooring, welding, vinyl seams, add	09651 610 8400	320	L.F.		
34	Flooring, vinyl composition tile, marbleized, 12" x 12" x 1/8"	09651 919 7350	26990	S.F.		
35	Paints & coatings, walls, concrete masonry units (CMU), smooth surface, first coat, latex, roller	09911 390 0410	10000	S.F.		
36	Exterior shutters, roll-up, manual operation, aluminum, 3' x 4', includes frame	10711 319 0020	3	Ea.		
37	Metal ductwork, fabricated rectangular, 500 to 1000 lb., aluminum alloy 3003-H14, incl fittings, joints, supports & allow for a flexible connections field sketches, excludes as-built drawings and insulation	23311 313 0120	1000	LB		
38	Fans, roof exhauster, centrifugal, aluminum housing, bird screen, back draft damper, direct drive, 1/4" S.P., 320 CFM, 12" galvanized curb, 11" sq. damper	23341 610 7100	1	Ea.		
39	Fans, ceiling fan, paddle blade air circulator, 6,500 CFM high, 4,000 CFM low, 52", includes 3 speed switch	23342 310 3040	1	Ea.		
40	Split ductless system, cooling only, single zone, wall mount, 2 ton cooling	23812 610 0150	18	Ea.		
41	Service & panel, residential, w/18 branch breakers, w/RGS conduit & wire, 200 amp, incl 24' SE-AL cable, service eye, meter socket	26059 010 1230	2	Ea.		
42	Switch devices, residential, single pole, #12/2, EMT & wire, 20', 20 amp, incl box & cover plate	26059 010 2280	1	Ea.		
43	Transformer, dry-type, ventilated, 3 phase 480 V primary 120/208 V secondary, 75 kVA	26221 310 3700	1	Ea.		
44	Transformer, dry-type, 3 phase 480 V primary 120/208 V secondary, 112.5 kVA	26221 310 3900	2	Ea.		
45	Generator set, diesel, 3 phase 4 wire, 277/480 V, 125 kW, incl battery, charger, muffler, & day tank, excl conduit, wiring, & concrete	26321 313 2400	1	Ea.		
46	Incandescent fixture, interior, ceiling/wall, surface mounted, metal cylinder, 75 W, incl lamps, mounting hardware and connections	26511 350 4900	29	Ea.		
47	Playground protective surfacing, resilient rubber surface, colors, 2" thick, poured in place	32181 613 0150	200	S.F.		
48	Playground protective surfacing, wood chip mulch, 6" deep	32181 613 0200	200	S.F.		
49	Chain link fence gates and posts, motor operators for gates, up to 20' wide swing, excludes electric wiring & excavation	32311 110 7815	1	Ea.		
50	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2-1/2" posts @ 10' OC, 8' high, includes excavation, in concrete, excludes barbed wire	32311 320 0920	640	L.F.		
51	Fence, chain link, gates & posts, line posts, galvanized, (1/3 post length in ground), 2-1/2" OD, 4', set in concrete, includes excavation	32311 330 6580	60	Ea.		
52	Fence, chain link, gates & posts, end posts, chain link fence, galvanized steel, 3" OD, 4', set in concrete, includes excavation	32311 330 6660	6	Ea.		
TOTAL						

NOTES:

<i>Itemized List - Pearl Larsen Elementary School</i>					<i>Updated 4/19/2018</i>	
	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost

1) EVERY LINE ITEM DETAILED ABOVE ARE CONSIDERED ADD/DELETES AND THE OWNER RESERVES THE RIGHT TO REMOVE ANY TASK AS IS DEEM REQUIRED TO MEET THE GOVERNMENT'S OBJECTIVE UNDER THIS REQUEST FOR PROPOSAL.

2) PRICES BEING SUBMITTED FOR WORK TO BE DONE SHALL INCLUDE THE CONTRACTOR'S OVERHEAD TAXES AND PROFIT ALONG WITH ALL COSTS FOR MATERIALS, EQUIPMENT AND MANPOWER NECESSARY TO FACILITATE PROPER, SAFE, AND TIMELY COMPLETION OF THE PROJECT.

3) UNIT PRICES SUBMITTED ON THIS ITEMIZED BID SHEET SHALL BE UTILIZED FOR ANY CREDITS OR DEBITS TO THE PROJECT; WHICH, IF NECESSARY, SHALL BE ADDRESSED AS A CHANGE ORDER TO THE PROJECT.

Itemized List - Alexander Henderson Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
1	Scaffolding, steel tubular, regular, frame, buy, 5' high x 5' wide	01542 370 1150	50	Ea.		
2	Scaffolding, steel tubular, regular, accessory, cross brace, buy	01542 370 1500	50	Ea.		
3	Scaffolding, steel tubular, regular, accessory, guardrail post, buy	01542 370 1550	50	Ea.		
4	Scaffolding, steel tubular, regular, accessory, screw jack & plate, buy	01542 370 1650	100	Ea.		
5	Scaffolding, steel tubular, regular, accessory, plank, buy, 2" x 10" x 16' long	01542 370 1800	25	Ea.		
6	Selective demolition, chain link fences & gates, fence, posts, steel in concrete	02411 362 1000	2	Ea.		
7	Selective demolition, chain link fences & gates, fence, fabric & accessories, fabric, to 8' high	02411 362 1100	1125	L.F.		
8	Selective demolition, rubbish handling, dumpster, 40 C.Y., 10 ton capacity, weekly rental, includes one dump per week, cost to be added to demolition cost	02411 919 0840	35	Dump		
9	Asbestos remediation, plans and methods, building survey, commercial	02821 339 0100	1	Ea.		
10	Asbestos abatement equipment & supplies, buy, airless sprayer unit, 2 gun	02821 341 0300	1	Ea.		
11	Preparation of asbestos containment area, separation barrier, 2" x 4" @ 16", 1/2" plywood each side, 12' high	02821 342 0310	300	S.F.		
12	Preparation of asbestos containment area, cover surfaces with polyethylene sheeting, walls, each layer, 6 mil, incl. glue & tape	02821 342 0560	300	S.F.		
13	Bulk asbestos removal, remove VAT and mastic from floor by hand, includes disposable tools & 2 suits & 1 respirator filter/day/worker	02821 343 5000	4711	S.F.		
14	OSHA testing, certified technician, min	02821 345 0100	2	Day		
15	OSHA testing, industrial hygienist, max	02821 345 0130	2	Day		
16	OSHA testing, asbestos sampling, PCM analysis, NIOSH 7400, maximum	02821 345 0210	5	Ea.		
17	Concrete crack repair, structural repair by epoxy injection (ACI RAP-1), suitable for horizontal, vertical and overhead repairs, up to 1/8" (0.125") wide x 6" deep, manual injection with 2-part epoxy cartridge, excludes prep	03013 071 1420	40	L.F.		
18	Unit masonry stabilization, structural fabric method, primer	04012 041 0310	5477	S.F.		
19	Unit masonry stabilization, structural fabric method, apply filling/leveling paste	04012 041 0320	5477	S.F.		
21	Cleaning masonry, new construction, medium construction dust, by chemical, brush and rinse, excludes scaffolding	04013 020 0220	67784	SF		
20	Cleaning masonry, light restoration, average soil, biological staining, by chemical, low pressure wash, brush and rinse, excludes scaffolding	04013 020 0270	5477	S.F.		
22	Metal floor decking, steel, non-cellular, composite, galvanized, 2" D, 18 gauge	05311 350 5400	430	S.F.		
23	Selective demolition, thermal and moisture protection, caulking/sealant, to 1" x 1" joint	07050 510 0020	1	L.F.		
24	Selective demolition, thermal and moisture protection, downspouts, including hangers	07050 510 0120	40	L.F.		
25	Selective demolition, thermal and moisture protection, gutters, metal or wood, edge hung	07050 510 0420	320	L.F.		
26	Selective demolition, thermal and moisture protection, roof edge, drip edge	07050 510 2220	425	L.F.		
27	Roof deck insulation, fiberboard high density, 1-1/2" thick, R3.8, fastening excluded	07221 610 0130	3291	S.F.		
28	Soffit, PVC, white, solid	07467 310 0300	40	S.F.		
29	APP modified bituminous membrane, smooth surface flashing, 170 mils, torched	07521 310 2300	3291	S.F.		
30	Steel downspouts, galvanized, round, corrugated, 5" diameter, 26 gauge	07712 310 5100	40	L.F.		
31	Galvanized steel gutters, half round or box, stock, 5" wide, 26 gauge	07712 330 2700	320	L.F.		
32	Aluminum drip edge, mill finish, .016" thick, 5" wide	07714 310 0020	425	L.F.		

Itemized List - Alexander Henderson Elementary School
Updated 4/19/2018

	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost
33	Door demolition, door frames, metal, remove	08050 510 2000	4	Ea.		
34	Window demolition, aluminum, to 25 S.F.	08050 520 0240	22	Ea.		
35	Frames, steel, knock down, hollow metal, single, 16 ga., up to 5-3/4" deep, 3'-0" x 6'-8"	08121 313 0025	4	Ea.		
36	Door, wood, architectural, flush, interior, hollow core, 7 ply, H.P. plastic laminate, 1-3/8", 3'-0" x 6'-8"	08141 609 1780	4	Ea.		
37	Windows, wood, awning, insulated glass, 40" x 28", incl. frames, screens & grilles	08521 020 0300	22	Ea.		
38	Ceiling demolition, suspended ceiling, mineral fiber, 2 x 2 or 2 x 4, remove	09050 510 1200	37356	S.F.		
39	Flooring demolition, vinyl composition tile, 12" x 12"	09050 520 0900	28000	S.F.		
40	Suspended acoustic ceiling tiles, mineral fiber tile, lay-in, fine texture, 2' x 2' or 2' x 4', 3/4" thick	09512 310 1125	37356	S.F.		
41	Acoustic ceiling grid, 2' x 2'	09532 330 0300	18725	S.F.		
42	Flooring, vinyl composition tile, marbled, 12" x 12" x 1/8"	09651 919 7350	28000	S.F.		
43	Paints & coatings, walls, concrete masonry units (CMU), smooth surface, first coat, latex, roller	09911 390 0410	5477	S.F.		
44	Selective demolition, countertop	12050 510 1200	68	L.F.		
45	Selective demolition, wall cabinets, wood, to 84" high	12050 510 3130	68	L.F.		
46	Custom cabinets, rule of thumb: kitchen cabinets, excl. counters & appliances, minimum	12322 310 9560	68	L.F.		
47	Countertops, stock, plastic laminate, 24" wide, includes backsplash, maximum	12362 313 0100	68	L.F.		
48	Air conditioner, split unit air conditioner, package unit, 3 ton, selective demolition	23050 510 0150	2	Ea.		
49	Metal ductwork, fabricated rectangular, 500 to 1000 lb., aluminum alloy 3003-H14, incl fittings, joints, supports & allow for a flexible connections field sketches, excludes as-built drawings and insulation	23311 313 0120	700	LB		
50	Self-contained single package A.C., air cooled, for free blow or duct, constant volume, 3 ton cooling, excludes remote condenser	23811 920 0200	2	Ea.		
51	Split ductless system, cooling only, single zone, wall mount, 2 ton cooling	23812 610 0150	54	Ea.		
52	Switch devices, residential, single pole, #12/2, EMT & wire, 20', 20 amp, incl box & cover plate	26059 010 2280	2	Ea.		
53	Transformer, dry-type, 3 phase 480 V primary 120/208 V secondary, 112.5 kVA	26221 310 3900	1	Ea.		
54	Generator set, diesel, 3 phase 4 wire, 277/480 V, 125 kW, incl battery, charger, muffler, & day tank, excl conduit, wiring, & concrete	26321 313 2400	1	Ea.		
55	High pressure sodium fixture, interior, recessed, round, 70 W, incl lamps and mounting hardware	26511 340 0700	4	Ea.		
56	Incandescent fixture, interior, ceiling/wall, surface mounted, metal cylinder, 75 W, incl lamps, mounting hardware and connections	26511 350 4900	55	Ea.		
57	Closed circuit television system (CCTV), industrial quality, for additional camera stations, add	28231 310 2600	2	Ea.		
58	Chain link fence gates and posts, motor operators for gates, up to 20' wide swing, excludes electric wiring & excavation	32311 110 7815	2	Ea.		
59	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2" posts @ 10' OC, 6' high, includes excavation, & concrete, excludes barbed wire	32311 320 0800	100	L.F.		
60	Fence, chain link industrial, galvanized steel, 6 ga. wire, 2-1/2" posts @ 10' OC, 8' high, includes excavation, in concrete, excludes barbed wire	32311 320 0920	1025	L.F.		
TOTAL						

NOTES:

1) EVERY LINE ITEM DETAILED ABOVE ARE CONSIDERED ADD/DELETES AND THE OWNER RESERVES THE RIGHT TO REMOVE ANY TASK AS IS DEEM REQUIRED TO MEET THE GOVERNMENT'S OBJECTIVE UNDER THIS REQUEST FOR PROPOSAL.

<i>Itemized List - Alexander Henderson Elementary School</i>					<i>Updated 4/19/2018</i>	
	Description	CSI Number	Qty	Unit	Unit Cost	Total Cost

2) PRICES BEING SUBMITTED FOR WORK TO BE DONE SHALL INCLUDE THE CONTRACTOR'S OVERHEAD TAXES AND PROFIT ALONG WITH ALL COSTS FOR MATERIALS, EQUIPMENT AND MANPOWER NECESSARY TO FACILITATE PROPER, SAFE, AND TIMELY COMPLETION OF THE PROJECT.

3) UNIT PRICES SUBMITTED ON THIS ITEMIZED BID SHEET SHALL BE UTILIZED FOR ANY CREDITS OR DEBITS TO THE PROJECT; WHICH, IF NECESSARY, SHALL BE ADDRESSED AS A CHANGE ORDER TO THE PROJECT.