



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT TWO (2)

June 4, 2018

TO:

**SUBJECT: IFB027DPWC18 (C) Road Repairs for Route 64
(Adjacent to the Rum Factory Road) Christiansted,
St. Croix.**

INSERT: New Bid Sheet Dated June 4, 2018

DELETE: Old Bid Sheet Dated April 23, 2018

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.

**GOVERNMENT OF
THE VIRGIN ISLANDS OF THE UNITED STATES**



ADDENDUM BID SHEET

PUBUC WORKS DEPARTMENT

5002 Estate Anna's Hope

Christiansted, St. Croix, V.I. 00820-4428

BID SHEET

Tel: (340)773. 1220

Fax: (340)773- 6865

PROJECT: Federal Route #64 Street Improvements (Near Rum Factory Road)

Page 1 of 1

DATE: Monday June 4, 2018

PREPARED BY: Haldor Farquhar

| ITEM | DESCRIPTION OF WORK | UNIT | QTY. | UNIT PRICE | COST |
|---|--|------|-------|------------|------|
| ROAD LENGTH = 5087 L.F. AVG. ROAD WIDTH = 27.5 L.F. | | | | | |
| 151.01 | Mobilization | L.S. | 1 | | |
| 305.01 | Full depth reclamation with cement. Process includes mill top 2-1/2", excavate 1 foot in depth to grade, mix existing grade with cement adding moisture content (slightly damp not slurry). *Refer to section 305 of The Standard Specifications for Construction of Roads and Bridges on Federal Highway Projects (FD-14) | C.Y. | 485 | | |
| 401.01 | Asphalt concrete pavement (hotmix) 2" in depth | TON | 1750 | | |
| 404.01 | Asphalt driveway adjustment 1 | TON | 20 | | |
| | Asphalt driveway adjustment 2 | TON | 60 | | |
| 412.06 | Asphalt tack coat (Grade, RS1) | GAL. | 971 | | |
| 413.01 | Roadway Milling (Material to given to VI Dept. of Public Works) | S.Y. | 15543 | | |
| 416.01 | Manhole ring adjustment | E.A. | 1 | | |
| 634.01 | Thermoplastic Direction Marking | E.A. | 10 | | |
| 635.01 | Temporary traffic control | L.S. | 1 | | |
| 718.12 | Thermoplastic Marking | L.F. | 20848 | | |
| TOTAL= | | | | | |

Duration of Project - 60 Calendar days