



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT ONE (1)

July 26, 2018

TO:

SUBJECT: IFB040DPWC18 (C) Road Repairs of Route 622 at Work & Rest, Christiansted St. Croix.

INSERT: New Bid Sheet Dated Wednesday, July 25, 2018

DELETE: Old Bid Sheet Dated Tuesday, June 5, 2018

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.



GOVERNMENT OF
THE VIRGIN ISLANDS OF THE UNITED STATES

PUBLIC WORKS DEPARTMENT
6002 Estate Anna's Hope
Christiansted, St. Croix, V.I. 00820-4428

DIVISION OF ENGINEERING

Tel: (340) 773-1290
Fax: (340) 773-6865

PROJECT:	Repairs to Rt. 622 at Estate Work & Rest
DATE:	Wednesday, July 25, 2018
PREPARED BY:	Eran Flemming

PAGE 1 OF 1

Revised



Repairs to Rt. 622 at Estate Work & Rest					
ROAD LENGTH = 4,985 L.F			ROAD WIDTH = 22 L.F		
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
15101	Mobilization	1.00	L.S		
41301	Milling of Roadway (2" Depth)	12186	S.Y		
41202	Tack Coat, Grade RS1	1462	GALLONS		
40101(A)	3" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	2047	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway	9970	L.F		
63401	Thermoplastic Pavement Markings, Type H (4" yellow) double yellow at center of roadway	9970	L.F		
41202	Temporary Traffic Control (Minor)	1	Lump Sum		
TOTAL =====>					

Total Cost of Project is _____

Licensed Contractor _____

Note: The undersigned Contractor acknowledges that the quantities included on the Bid Sheet are estimated values. It is the Contractor's responsibility to ascertain that the required material and quantities are included in the Bid Sheet in the event that there is a discrepancy between what the Contractor estimates is required to complete said project. Any discrepancies in values or material required must be identified at the time of the Pre-Bid meeting. Once the contract is executed, the Contractor will be required to complete the project based on selected bidder's contractual agreement cost.

Eran Flemming 7/26/18
PUBLIC WORKS DEPARTMENT
ST. CROIX
VIRGIN ISLANDS