



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT ONE (1)

August 9, 2018

TO:

SUBJECT: IFB047DPWC18 (C) Repairs to Estate Diamond Roads, Frederiksted, St. Croix.

INSERT: New Revised Bid Sheet Dated Wednesday, August 8, 2018

DELETE: Old Bid Sheet Dated Wednesday, June 27, 2018

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.



**GOVERNMENT OF
THE VIRGIN ISLANDS OF THE UNITED STATES**

PUBLIC WORKS DEPARTMENT
6002 Estate Anna's Hope
Christiansted, St. Croix, V.I. 00820-4428

DIVISION OF ENGINEERING

Tel: (340) 773-1290
Fax: (340) 773-6865

PROJECT:	Repairs Estate Diamond Roads, Frederiksted, St. Croix
DATE:	Wednesday, August 08, 2018
PREPARED BY:	Eran Flemming

PAGE 1 OF 1

Revised



Repairs to Estate Diamond Roads					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
15101	Mobilization	1	L.S		
ROAD NO.1	LENGTH = 2,080 L.F	WIDTH = 20 L.F			
41301	Road Reconditioning	20.8	STA.		
41202	Tack Coat, Grade RS1	556	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	518	Tons		
ROAD NO.2	LENGTH = 2,000 L.F	WIDTH = 20 L.F			
41301	Road Reconditioning	20	STA.		
41202	Tack Coat, Grade RS1	533	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	498	Tons		
20401	Roadway Excavation (100'Lx20'Wx12"). Failed section of Roadway	75.00	C.Y		
30101	Untreated Aggregate Course (Base/Subbase)for cut areas	75.00	C.Y		
ROAD NO.3	LENGTH = 1000 L.F	WIDTH = 20 L.F			
41301	Road Reconditioning	10	STA.		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	249	Tons		
41202	Tack Coat, Grade RS1	267	GALLONS		
ROAD NO.4	LENGTH = 930 L.F	WIDTH = 20 L.F			
41301	Road Reconditioning	9.3	STA.		

41202	Tack Coat, Grade RS1	248	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness	231	Tons		
ROAD NO.5	LENGTH = 1,500 L.F	WIDTH = 20 L.F			
41301	Road Reconditioning	15	STA.		
41202	Tack Coat, Grade RS1	400	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness	373	Tons		
ROAD NO.6	LENGTH = 930 L.F	WIDTH = 20 L.F			
41301	Road Reconditioning	9.3	STA.		
41202	Tack Coat, Grade RS1	232	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness	248	Tons		
ROAD NO.7	LENGTH = 690 L.F	WIDTH = 20 L.F			
41301	Road Reconditioning	6.9	STA.		
41202	Tack Coat, Grade RS1	184	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A"Grade "D" Type I Smoothness	172	Tons		
63501	Temporary Traffic Control	1	LS		
			TOTAL =====>		

DURATION FOR PROJECT - 45DAYS

Total Cost of Project is _____

Licensed Contractor _____

Note: The undersigned Contractor acknowledges that the quantities included on the Bid Sheet are estimated values. It is the Contractor's responsibility to ascertain that the required material and quantities are included in the Bid Sheet in the event that there is a discrepancy between what the Contractor estimates is required to complete said project. Any discrepancies in values or material required must be identified at the time of the Pre-Bid meeting. Once the contract is executed, the Contractor will be required to complete the project based on selected bidder's contractual agreement cost.