



# Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587



[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)

## AMENDMENT ONE (1)

**August 29, 2018**

**TO:**

\_\_\_\_\_

\_\_\_\_\_

**SUBJECT: IFB060DPWC18 (C) Repairs to Christiansted Roads,  
St. Croix.**

**INSERT: New Bid Sheet dated Wednesday, August 29, 2018**

**DELETE: Old Bid Sheet dated Monday, August 13, 2018**

**All other terms and conditions remain the same.**

**A copy of this amendment must be returned with your bid.**



**GOVERNMENT OF  
THE VIRGIN ISLANDS OF THE UNITED STATES**

PUBLIC WORKS DEPARTMENT  
6002 Estate Anna's Hope  
Christiansted, St. Croix, V.I. 00820-4428

Tel (340) 773-1290  
Fax (340) 773-6865

DIVISION OF ENGINEERING

<b>PROJECT:</b> Christiansted Road Repairs	<b>PG. NO.1</b>
<b>DATE:</b> Wednesday, August 29, 2018	
<b>PREPARED BY:</b> Eran Flemming	Revised

Road Repairs in the Town of Christiansted					
ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
<b>Queen Street Section -1 ROAD LENGTH = 1,375' ROAD WIDTH = 20'</b>					
41301	Milling of Roadway (2" Depth)	3056	S.Y		
41202	Tack Coat, Grade RS1	367	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness for	342	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	2750	L.F		
<b>Queen Street Section -2 ROAD LENGTH = 615' ROAD WIDTH = 16'</b>					
41301	Milling of Roadway (2" Depth)	1093	S.Y		
41202	Tack Coat, Grade RS1	131	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	123	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	1230	L.F		
<b>Hill Street - ROAD LENGTH = 2,429' ROAD WIDTH = 20'</b>					
41301	Milling of Roadway (2" Depth)	5398	S.Y		
41202	Tack Coat, Grade RS1	648	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	605	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	4858	L.F		
<b>Road Connecting Strand and Kingstreet in the vicinity of Plot 44 Kingstreet Length = 190' Width = 24'</b>					
41301	Milling of Roadway (2" Depth)	507	S.Y		
41202	Tack Coat, Grade RS1	61	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	57	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	380	L.F		

**SUB-TOTAL**

<b>PROJECT:</b>	Christiansted Road Repairs	<b>PG. NO.2</b>
<b>DATE:</b>	Monday, August 13, 2018	
<b>PREPARED BY:</b>	Eran Flemming	

**Christiansted Road Repairs**

ITEM	DESCRIPTION OF WORK	QTY.	UNITS	UNIT PRICE	COST
<b>Market Street, from the intersection of Company to East Street. Rd. Length=591 Width = 24'</b>					
41301	Milling of Roadway (2" Depth)	1576	S.Y		
41202	Tack Coat, Grade RS1	189	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	177	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	1182	L.F		
<b>East Street - ROAD LENGTH = 2,025' ROAD WIDTH = 24'</b>					
41301	Milling of Roadway (2" Depth)	5400	S.Y		
41202	Tack Coat, Grade RS1	648	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	605	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	4050	L.F		
<b>Prince Street - ROAD LENGTH = 1,693' ROAD WIDTH = 24'</b>					
41301	Milling of Roadway (2" Depth)	4515	S.Y		
41202	Tack Coat, Grade RS1	542	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	506	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" yellow) double yellow at center of roadway	1640	L.F		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	3386	L.F		
<b>Strand Street - Road Section 1 Length= 654' Width = 12'</b>					
41202	Tack Coat, Grade RS1	105	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	98	Tons		
<b>Strand Street - Road Section 2 Length= 495' Width = 20'</b>					
41301	Milling of Roadway (2" Depth)	1100	S.Y		
41202	Tack Coat, Grade RS1	132	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	123	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	990	L.F		
<b>West Street - ROAD LENGTH = 640' ROAD WIDTH = 24'</b>					
41301	Milling of Roadway (2" Depth)	1707	S.Y		

41202	Tack Coat, Grade RS1	205	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A" Grade "D" Type I Smoothness	191	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	1280	L.F		
63401	Thermoplastic Pavement Markings, Type H (4" yellow) double yellow at center of roadway	1640	L.F		
Smith Street - ROAD LENGTH = 400' ROAD WIDTH = 20'					
41202	Tack Coat, Grade RS1	107	GALLONS		
40101(A)	2" Asphalt Concrete Pavement, CL- "A" Grade "D" Type I Smoothness	100	Tons		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	800	L.F		
63401	Thermoplastic Pavement Markings, Type H (4" yellow) double yellow at center of roadway	800	L.F		
				SUB-TOTAL	
41202	Temporary Traffic Control (Minor)	1	Lump Sum		
15101	Mobilization (5%)	1	Lump Sum		
				TOTAL	

Licensed Contractor \_\_\_\_\_

Contractor's Signature \_\_\_\_\_ Date \_\_\_\_\_

**Note: The undersigned Contractor acknowledges that the quantities included on the Bid Sheet are estimated values. It is the Contractor's responsibility to ascertain that the required material and quantities are included in the Bid Sheet in the event that there is a discrepancy between what the Contractor estimates is required to complete said project. Any discrepancies in values or material required must be identified at the time of the Pre-Bid meeting. Once the contract is executed, the Contractor will be required to complete the project based on selected bidder's contractual agreement cost.**