



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT ONE (1)

August 29, 2018

TO:

SUBJECT: IFB062DPWC18 (C) Repairs to Casper Holstein Drive, Frederiksted, St. Croix.

INSERT: New Bid Sheet dated Wednesday, August 29, 2018

DELETE: Old Bid Sheet dated Thursday, August 9, 2018

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bid.



**GOVERNMENT OF
THE VIRGIN ISLANDS OF THE UNITED STATES**

PUBLIC WORKS DEPARTMENT
6002 Estate Anna's Hope
Christiansted, St. Croix, V.I. 00820-4428

DIVISION OF ENGINEERING

Tel: (340) 773-1290
Fax: (340) 773-6865

PROJECT:	<i>Repairs to Casper Holstein Drive</i>	PAGE 1 OF 1
DATE:	Wednesday, August 29, 2018	
PREPARED BY:	Eran Flemming	REVISED



ITEM	DESCRIPTION OF ITEMS	UNITS	QTY.	UNIT PRICE	COST
Repairs to Casper Holstien Drive					
Total Road Length = 3,325' Road Width = 24'					
305.01	Full depth reclamation of existing pavement and base. Pulverize 12" of existing pavement and base in-place, shape & compact mix to produce a road base. Work to be done in accordance with subsection 304.05 of the FP-14. Apply an inverted prime in accordance to 411.06 from the FP-14, Use undiluted emulsified asphalt at a rate of 0.30 gallons/SY and aggregate distribution at a rate of 0.25lbs/SY.	S.Y	8,867		
41202	Tack Coat, Grade RS1	Gallons	1064		
40101(A)	4" Asphalt Concrete Pavement, CL-"A"Grade "D" Type I Smoothness	Tons	1986		
63401	Thermoplastic Pavement Markings, Type H (4" white) at edge of roadway)	L.F	6650		
63401	Thermoplastic Pavement Markings, Type H (4" yellow) double yellow at center of roadway	L.F	6650		
60901	Removal of low water crossing (35'x20')	S.Y	78		

60901	structural concrete for low water crossing (35'x20'x6"), to include all forming, rebar's and granular fill	S.Y	78		
63501	Temporary Traffic Control	L.S	1		
15101	Mobilization	L.S	1		
TOTAL =====>					

Total Cost of Project is _____

Licensed Contractor _____

Contractor's Signature _____ Date _____