



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, SUITE 4, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.777.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



AMENDMENT Three (3)

January 22, 2019

TO:

**SUBJECT: IFB011DPWC19(C) Melvin Evans Highway (route 66)
Pavement Rehabilitation and Safety Improvements
Project VI-0066 (014) St. Croix, V.I.**

INSERT: New Bid Schedule: D 2 – D 6

DELETE: Old Bid Schedule

All other terms and conditions remain the same.

A copy of this amendment must be returned with your bi

BID SCHEDULE

IFB NO. _____ PROJECT NO. # VI-0066(014)

CONTRACTOR'S NAME: _____

CITY _____ STATE _____ ZIP CODE _____

The undersigned Contractor proposed to furnish all labor, tools, equipment, machinery, and supplies for the Melvin H. Evans Highway Pavement Rehabilitation to USVI Highway 66 subject to all conditions and requirements of the Standard Specifications for Construction of Roads and Bridges on Federal Highway Projects, FP-14 as revised and amended and the Contract Documents.

ITEM NUMBER	APPROX QTY	UNITS	ITEM / TASK DESCRIPTION	UNIT PRICE DOLLARS/CENTS	AMOUNT DOLLARS/CENTS
15101-0000	1	LPSM	Mobilization _____ _____ _____		
15201-0000	1	LPSM	Construction Survey and Staking _____ _____ _____		
15401-0000	1	LPSM	Contractor Testing _____ _____ _____		
15701-0000	1	LPSM	Soil Erosion Control _____ _____ _____		

15901	1	LPSM	On the Job Training		
20102-0000	75	SQYD	Selective Clearing at washout _____ _____		
20103-0000	7,698	LNFT	Clearing and Grubbing of Shoulders and Median Curb _____ _____ _____		
			Removal of Signal & Obstructions _____ _____ _____		
20301-3100	2	EACH	Removal of structures & Obstructions- Median Curb Concrete _____ _____ _____		
20302-0300	100	LNFT	Removal of Structures and Obstructions-Guardrail _____ _____ _____		
20302 -1200	1,812	LNFT	Repair Washout Area _____ _____ _____		
20420-0000	1	SQYD	Warm Mix Asphalt concrete pavement, Class B, 3" _____ _____ _____		
40201-0200	5,300	TON	Tack Coat Grade RS-1		
41201	4000	GALS			

			Asphalt Pavement Milling, 3" depth		
41301-0800	31,402	SOYD			
			Minor Concrete Structures-CURB		
60101-0000	114	LNFT			
			Waterway- 4' concrete, 4" depth		
60101-0000	4,115	LNFT			
			Minor Concrete Structures- Energy Dissipater		
60103-0000	1	EACH			
			Culvert & Drainage-Install 18 inch HDPE DRAIN PIPES		
60201-0600	107	LNFT			
			Culvert & Drainage -Install 18 inch CONCRETE ELLIPTICAL PIPES		
60202-0200	35	LNFT			
			Mainhole Inlet & Catch basin, Type D		
60404-3000	3	EACH			
			Repair Curb Inlets in Median		
60706-0000	3	EACH			
			Guardrail system G4, type II, class B, Steel posts with button reflectors		
61701-1350	1,812	LNFT			

			Guardrail-Terminal end, type Round		
61703-2000	9	EACH	Guardrail-Terminal end, type F.E.A.T.		
61703-1000	3	EACH			
			Guardrail-Terminal Section Median Impact Attenuator-REACT 350		
61711-0000	1	EACH			
			Pavement markings, type H 4" Solid White		
63401-1500	9,462	LNFT	Pavement markings, type H 4" Solid Yellow		
63401-1500	8,100	LNFT	Pavement markings, type H 4" Broken White		
63401-1600	7,422	LNFT	Pavement markings, type H Turn Arrow		
63405-2900	10	EACH	Pavement markings, type H Straight Arrow		
63405-1950	22	EACH	Pavement markings, type H, Straight/Turn Arrow		
63405-3000	2	EACH			

			Pavement markings, type H, 24" Solid White		
63405-1500	270	LNFT			
			Permanent Pavement Markings-Raised Pavement Markers		
63406-0200	750	EACH			
			Temporary traffic control		
63501-0000	1	LP SM			

IFB NO. _____ PROJECT NO. # VI-0066(014)

ATTENTION: See notes at the beginning of this unit price schedule.

TOTAL AMOUNT OF THIS PROPOSAL, BASED ON ENGINEER'S ESTIMATE OF QUANTITIES IS AS FOLLOWS:

_____ DOLLARS AND _____ CENTS

\$ _____

 BIDDER'S SIGNATURE