



Department of Property & Procurement

Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820

8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828

ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.774.9587

[HTTP://DPP.VI.GOV](http://DPP.VI.GOV)



March 18, 2020

AMENDMENT FOUR (4)

IFB026DPWC20 (C)- Road Repairs in the Town of Frederiksted, St. Croix, USVI

INSERT: QUESTIONS AND ANSWERS

Question: What is the expected date of the project and how does it relate to the current WAPA waterline project?

Answer: The expected date of commencement of the project is roughly in the next three (3) months. WAPA will be replacing the water lines. The roadway will be patched after the water lines are installed.

Question: Is there a SWPPP required for this project?

Answer: No.

Question: Is there any surveying or staking required for the project? If so, will an item be added to the bid sheet?

Answer: You are expected to station the roads, but no major survey is expected.

Question: Is there any dust control required for the project? If so, will an item be added to the bid sheet?

Answer: There are no major dust control for the project except for when the milling is being executed.

Question: Is there any erosion control or inlet protection required in the project? If so, will an item be added to the bid sheet?

Answer: No

Question: Is there any pedestrian control required for the project? If so will an item be added the bid sheet?

Answer: No.

Question: Has there been any concern to roadway stability/has any geotechnical report or borings been done for the project?

Answer: WAPA will be excavating some of the roadway; however, they are expected to recompact the roadway.

Question: Since the contract only calls for the milling and replacing of 2 inches of HMA surface and not full roadway reconstruction, how will any de-stabilized area in the project be identified and addressed?

Answer: The road should not be destabilized because WAPA shall re-compact the roadway once the water lines are installed.

Question: Can a copy of the asphalt repairs detail for the newly installed water line be provided?

Answer: A copy of the plans was provided to DPW, but the patching detail is mandated by DPW. A copy of the detail will be provided.

Question: Will the awarded contractor be able to receive as built drawing for the newly installed waterline?

Answer: DPW have a copy of the proposed drawings and we will try to obtain the As-Built drawings.

**All other terms and conditions remain the same.
A copy of this amendment must be returned with your bid.**