

## GOVERNMENT OF THE VIRGIN ISLANDS DEPARTMENT OF EDUCATION

## **ADDENDUM 4: Add Alternates**

Renovation of the Wheatley Skills Center St. Thomas/ St. John School District

## **ADD ALTERNATE ITEMS**

No.	Description	Specifics	Qty.	Units	Unit Price	Total Price
A7	<b>METAL FRAMING</b> - Install metal roof deck – fasten to structure to resist design wind loads, 1 inch, 24 gauge, corrugated, galv. deck	Main Building	2600	SF		
A8		Annex Building	1620	SF		
	STATIC WALL SYSTEMS					
A9	Install 2x6 stud walls x 10' high, 16" o.c., neatly sanded and finished	Pressure treated lumber	1480	SF		
A9.1	Install 5/8" fire rated clear acrylic panels		1480	SF		
A10	Install 2x6 stud walls x 10' high, 16" o.c.	Pressure treated lumber	560	SF		
A10.1	Install 5/8" moisture resistant fire rated gypsum wallboard		1120	SF		
	INSULATION					
A11	6" thick fiberglass batt insulation in walls (to match #38 walls)		1410	SF		
A12	6" thick fiberglass batt insulation in walls (to match #A10 walls)		560	SF		
A13	<b>WINDOWS</b> – Replace existing windows with New 36"h x 58" alum. framed windows with hurricane resistant glazing Low E glass	Main Building 2 <sup>nd</sup> Floor	24	EA		

framed windows with nurricane resistant glazing Low E glass	Floor					
The undersigned Construction Contractor examined the site condi	itions thoroughly, a	and is able ar	nd willir	ng to perforr	n the abov	⁄e
described						
Certified Correct:						
//: 10 · · · · · · · · · · ·	<u> </u>				•	
(Licensed Contractor's Signature)	(Date)					
(Company)					i	
(Company)						