

# **Department of Property&Procurement**

## Government of the United States Virgin Islands

3274 ESTATE RICHMOND, CHRISTIANSTED, U. S. VIRGIN ISLANDS 00820 8201 SUB BASE, 3RD FLOOR, ST. THOMAS, U. S. VIRGIN ISLANDS 00802

ST. CROIX MAIN OFFICE: 340.773.1561 | ST. THOMAS MAIN OFFICE: 340.774.0828 ST. CROIX FAX: 340.773.0986 | ST. THOMAS FAX: 340.774.9587

HTTP://DPP.VI.GOV

May 21, 2020

**Amendment #1- IFB031VIPDT20 (C)** Additional Concrete Work at the Support Services Building, located at (Parcel B4 Submarine Base No. 6 Southside Qtr), for the Virgin Islands Police Department on St. Thomas, Virgin Islands.

Delete: Previous Bid Schedule Information

**Insert:** Updated Bid Schedule Information

#### **Questions and Answers**

1. Please confirm that all concrete shall be 3,000 psi at 28 days.

No, 3,500 psi at 28 days.

2. Please confirm that all rebar will 60 psi Grade 60.

Yes, 60 psi, Grade 60.

3. Please confirm that the erosion control measures (Silt fence and construction entrance) will be included in No.208-03 Remove Existing Dirt of the Big Schedule.

Please see the updated Bid Schedule Item No. 157-03.

4. Please indicate the location of the driveway on the drawing.

The Driveway entrance is located at the North-West corner of the site between the two columns. The entrance is approximately 16 feet.

5. Please specify the Contractor Testing Required.

Please conduct Slump Test, Cylinder breaks at 7, 14 & 28 days to verify concrete strength. Provide concrete tickets to verify cubic yards delivered to the site.

6. Please specify the stone shown on the detail drawing behind the retaining wall.

ICF Crushed Stone 3" to 4" to weep Holes Typ.

7. Please specify the interior and exterior replacement doors.

Only (11) Interior Doors will be replaced.

Door Specs. 36"x80" Metal Door with Vision Lite Glass. The contractor must provide submittal for approval.

8. Please confirm that the concrete slab (10'x10'x4") is to be demolished.

The concrete slab is to be demolished and replaced with the concrete that will cover the proposed area for the parking lot.

9. Please confirm the number of doors and frames to be removed and replaced is 11 (not 14 as in the Bid Schedule).

The total number of doors are (11). Interior Doors only. Please see the updated Bid Schedule.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

BIDDERS MUST ACKNOWLEDGE RECEIPT OF THIS AMENDMENT WITH THEIR BID PROPOSAL.



### **BID SCHEULE**

#### ADDITIONAL CONCRETE WORK FOR THE RENOVATON OF THE SUPPORT SERVICES FOR THE VIPD

PARCEL B4 SUBMARINE BASE No.6 SOUTHSIDE QUARTER, ST. THOMAS, VIRGING ISLANDS

			NUMBERS	WORDS	
<u>No.</u>	DESCRIPTION	<u>UNITS</u>	QTY. UNIT PRICE	<u>UNIT PRICE</u>	TOTAL (\$)
151-01	MOBILIZATION	LS	1.00		
154-01	CONTRACTOR TESTING	LS	1.00		
104-01			1.00		
157-03	SILT FENCE - EROSION CONTROL	LF	65.00		
208-03	REMOVE OF EXISTING DIRT	CY	72.00		
208-01	EXCAVATION	CY	58.00		
301-01	BACKFILL / COMPACTED	CY	61.00		
258-03	REINFORCED CONCRETE RET. WALL :				
	A FOOTING	CY	24.00		
	B WALL	CY	19.00		
258-04	8" RETAINING CONCRETE CURB	CY	1.00		
	(Including:excavation,footing,wall,aggregate)				
301-01	AGGREGATE BASE - 6" COMPACTED	CY	14.00		
501-01	REINFORCED PORTLAND CEMENT	CY	84.00		
	CONCRETE PAVE - 6" THICKNESS				
	(Including forms and rebar, Parking area)				
608-01	PAVED WATERWAY (CONC. SWALE)	SY	27.00		
608-01	MISC. WHEEL STOPS. 8'-0" LENGTHS	EA	8.00		
634-01	THERMOPLASTIC PAVEMENT MAR-	LF	162.00		
	KINGS. (Type H (4" White Parking)				
5500	REMOVE/REPLACE EXISTING EXTERIOR	EA	11.00		
	& INTERIOR DOORS FOR METAL DOORS AND FRAMES: 36" X 80"				
	TOTAL (NUMBERS)				
	CONTRACTOR'S SIGNATURE:				